

0050166

---

**Pacific Northwest  
National Laboratory**

Operated by Battelle for the  
U.S. Department of Energy

**Proposal for Fiscal Year 1999 Vadose  
Zone Monitoring and Guidance for  
Subsequent Years for Liquid Waste  
Disposal Facilities**

D. G. Horton  
S. P. Reidel  
G. V. Last

November 1998



Prepared for the U.S. Department of Energy  
under Contract DE-AC06-76RLO 1830

---

## DISCLAIMER

This report was prepared as an account of work sponsored by an agency of the United States Government. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof, or Battelle Memorial Institute.

PACIFIC NORTHWEST NATIONAL LABORATORY  
*operated by*  
BATTELLE  
*for the*  
UNITED STATES DEPARTMENT OF ENERGY  
*under Contract DE-AC06-76RLO 1830*

Printed in the United States of America

Available to DOE and DOE contractors from the  
Office of Scientific and Technical Information, P.O. Box 62, Oak Ridge, TN 37831;  
prices available from (615) 576-8401.

Available to the public from the National Technical Information Service,  
U.S. Department of Commerce, 5285 Port Royal Rd., Springfield, VA 22161



This document was printed on recycled paper.

**Proposal for Fiscal Year 1999 Vadose Zone  
Monitoring and Guidance for Subsequent Years  
for Liquid Waste Disposal Facilities**

D. G. Horton  
S. P. Reidel  
G. V. Last

November 1998

Prepared for  
the U.S. Department of Energy  
under Contract DE-AC06-76RLO 1830

Pacific Northwest National Laboratory  
Richland, Washington 99352

**THIS PAGE INTENTIONALLY  
LEFT BLANK**

## Summary

This document is prepared by Pacific Northwest National Laboratory<sup>1</sup> in response to a U.S. Department of Energy request for a proposal describing vadose zone monitoring of liquid waste disposal facilities that are not part of the Tank Waste Remediation System. This document includes the needs and objectives of vadose zone monitoring and provides proposed rationale and general framework for vadose zone monitoring of past-practice cribs, ditches, trenches, and other disposal facilities. The monitoring described herein will be modified as necessary so as to be incorporated into the Groundwater/Vadose Zone Integration Project.

The proposed vadose zone monitoring complements the 200 Areas soil remediation strategy developed by the Hanford Site's Environmental Restoration Contractor. Most 200 Areas past-practice, liquid waste disposal facilities are slated for remediation, ranging from complete cleanup to in-place management. The monitoring discussed in this proposal will track vadose zone contamination until remedial actions can occur. Also, if in some instances vadose zone contamination is managed in place, periodic monitoring to assess the effectiveness of that remedial decision may be necessary. It is expected that this proposal will undergo changes as the priorities and activities of Hanford Site environmental restoration evolve.

This report has been issued in hard-copy and electronic formats. The electronic version of the hard-copy document is available on the Internet at <http://www.pnl.gov/vadose/index.html>.

---

<sup>1</sup> Pacific Northwest National Laboratory is operated by Battelle for the U.S. Department of Energy.

**THIS PAGE INTENTIONALLY  
LEFT BLANK**

## **Acknowledgments**

This document benefited from the participation of K. R. Fecht, G. W. Gee, V. G. Johnson, A. J. Knepp, F. M. Mann, C. J. Murrey, R. J. Serne, R. M. Smith, M. D. Sweeney, A. L. Ward, and G. Whelen in the data quality objectives process. Their comments, thoughts, and ideas contributed much to the authors' conceptual implementation of vadose zone monitoring.

**THIS PAGE INTENTIONALLY  
LEFT BLANK**



# Contents

Summary .....	iii
Acknowledgments .....	v
1.0 Introduction .....	1.1
1.1 Scope .....	1.2
1.2 Document Organization .....	1.3
2.0 Vadose Zone Geology .....	2.1
2.1 Ringold Formation .....	2.1
2.2 Intervening Plio-Pleistocene Unit, Pre-Missoula Gravels, and Early “Palouse” Soil .....	2.1
2.3 Hanford Formation .....	2.3
2.4 Holocene Deposits .....	2.3
2.5 Discontinuities .....	2.4
3.0 Past Vadose Zone Monitoring at Hanford .....	3.1
3.1 Gross Gamma-Ray Logging .....	3.1
3.2 Spectral Gamma-Ray Logging .....	3.2
3.3 Neutron Logging .....	3.2
3.4 Compilations of Logging Data .....	3.2
3.5 Other Characterization and Monitoring Data Sources .....	3.3
3.6 Uses of Historical Data for Current and Future Monitoring .....	3.3
4.0 Data Quality Objectives Process .....	4.1
4.1 Introduction .....	4.1
4.2 Description of DQO Process and Limitations .....	4.1
4.3 Data Requirements and Regulatory Drivers .....	4.2

4.4	Statement of Problem .....	4.2
4.4.1	Conceptual Model Considerations.....	4.3
4.4.2	Resource Constraints .....	4.4
4.5	Decision and Expected Action.....	4.4
4.6	Decision Inputs .....	4.4
4.7	Study Boundaries.....	4.6
4.8	Decision Rule.....	4.6
4.8.1	Statistical Parameters of Interest.....	4.8
4.8.2	Action Level or Measurement Threshold .....	4.9
4.8.3	Alternative Actions .....	4.9
4.9	Limits on Decision Errors.....	4.9
4.10	Optimizing Sampling Design .....	4.10
4.11	Site-Specific Vadose Zone Monitoring Strategy .....	4.11
5.0	Site Prioritization .....	5.1
5.1	Prioritization Process .....	5.1
5.2	Prioritization Results .....	5.1
6.0	Monitoring and Analysis.....	6.1
6.1	Vadose Zone Monitoring.....	6.1
6.1.1	Facilities to be Monitored .....	6.1
6.1.2	Select Constituents of Concern.....	6.1
6.1.3	Select Monitoring Methods .....	6.2
6.1.4	Determine Monitoring Network .....	6.3
6.1.5	Premonitoring Activities.....	6.7
6.1.6	Acquire Monitoring Services.....	6.7
6.1.7	Data Reduction, Data Analysis, and Data Interpretation .....	6.9
6.1.8	Data Management.....	6.9
6.1.9	Reporting .....	6.10
7.0	References.....	7.1
Appendix A - Quality Assurance Project Plan .....		A.1
Appendix B - Site Prioritization .....		B.1
Appendix C - Proposed Fiscal Year 1999 Vadose Zone Monitoring Activities .....		C.1

## Figure

2.1	Suprabasalt Stratigraphy at the Hanford Site .....	2.2
-----	--	-----

## Tables

4.1	Conceptual Model Parameters of Interest .....	4.9
4.2	Elements of Vadose Zone Monitoring .....	4.11
6.1	Compilation of Cleanup Levels from Operable Unit Records of Decision for Vadose Zone Monitoring Constituents of Concern .....	6.2
6.2	Monitoring Methods Applicable to Constituents of Interest.....	6.4

**THIS PAGE INTENTIONALLY  
LEFT BLANK**

## 1.0 Introduction

The U.S. Department of Energy's (DOE's) Hanford Site has the most diverse and largest amounts of radioactive waste in the United States. These radioactive wastes came from various sources: 1) plutonium and uranium recovery processing of approximately 100,000 Mtu of irradiated fuel, 2) tank waste processing for radionuclide recovery, and 3) miscellaneous sources (e.g., laboratories and reactor decontamination solutions). The neutralized wastes contained sodium nitrate, sodium hydroxide, sodium aluminate, sodium phosphate, large amounts of organic materials, and approximately 260 MCi of radioactivity.

Much of the radioactive waste was stored in 149 single-shell tanks and 28 double-shell tanks. However, the majority of the effluent volume was disposed to the soil column either to absorb the liquid and its hazardous or radioactive material (specific retention facilities) or to chemically react (adsorption/precipitation) with the materials (cribs, french drains, ponds, etc.).

DOE Order 5400.1, *General Environmental Protection Program*, specifies that environmental surveillance shall be conducted to monitor the effects of DOE activities on onsite and offsite environmental and natural resources. The environmental surveillance, in part, is to 1) verify compliance with applicable environmental laws and regulations and with commitments in environmental impact statements and environmental assessments, 2) characterize and define trends in the physical and chemical condition of environmental media, 3) establish a baseline of environmental quality, and 4) identify and quantify new or existing environmental quality problems. The *Environmental Monitoring Plan, United States Department of Energy, Richland Operations Office* (DOE 1997a) defines the requirements for effluent monitoring and near-facility surface and groundwater monitoring necessary to accomplish the goals of DOE Order 5400.1.

The Hanford Groundwater Monitoring Project was started in 1997 to integrate the groundwater and vadose zone monitoring activities to fulfill the goals and objectives of the *Resource Conservation and Recovery Act of 1976* (RCRA), the *Comprehensive Environmental Response, Compensation, and Liability Act of 1980* (CERCLA), DOE Orders, and the Washington Administrative Code. Groundwater monitoring at that time was well established partly because of the emphasis placed on groundwater by environmental regulations. Vadose zone monitoring, which lacks a similar emphasis, was limited to geophysical monitoring at dry wells within single-shell tank farms and dry wells and groundwater wells at a few liquid effluent disposal facilities. No strategy for sitewide and source-specific vadose zone monitoring existed.

This document was prepared at the request of the DOE to provide a proposal describing vadose zone monitoring, how the monitoring project would be melded into the sitewide Groundwater/Vadose Zone Integration Project, and how the data obtained from the monitoring will be used.

To that end, this proposal provides a rationale and general framework for vadose zone monitoring to detect new sources of contamination and track the movement of existing contamination for the protection of groundwater. This monitoring proposal addresses some of the elements of a source-specific vadose

zone monitoring strategy and describes the technical and administrative controls on vadose zone monitoring in support of the Hanford Groundwater Monitoring Project. Information obtained from implementing this proposal and subsequent site-specific vadose zone monitoring plans will be integrated with other monitoring and technical activities within the Hanford Groundwater Monitoring Project, the Groundwater/Vadose Zone Integration Project, and current and future environmental remediation activities.

The dominant mission at the Hanford Site is environmental remediation. One important connection between the Hanford Groundwater Monitoring Project vadose zone monitoring and the Hanford Site remediation activities is through the process identified in the 200 Areas soil remediation strategy (DOE 1996). That strategy recognized that most 200 Areas past-practice liquid disposal facilities will undergo some form of remediation, ranging from complete cleanup to in-place management. The vadose zone monitoring discussed in this proposal tracks vadose zone contamination until those remedial actions can occur. Also, if in some instances vadose zone contamination is managed in place, periodic monitoring to assess the effectiveness of that remedial decision may be necessary. It is expected that this proposal will undergo changes as the priorities and restoration activities evolve.

As the vadose zone monitoring project discovers needs for baseline data against which to monitor or needs based on existing borehole surveys, those needs can be passed to the 200 Areas soil investigations for inclusion in appropriate limited field investigations. Any new characterization facility (e.g., boreholes) may then become additional monitoring points for the vadose project.

This document is not intended to delineate all the specific details of monitoring for any particular site. That scope belongs to the site-specific monitoring plans that will be developed for each vadose zone monitoring task. Instead, this proposal is intended to provide a framework and general criteria directing site-specific monitoring plans and a path to achieve site-specific vadose zone monitoring.

A modified data quality objectives (DQO) process was used as a major source of information to produce this proposal. The results of the DQO process and subsequent reviews of this proposal resulted in a road map leading from the general guidance of this proposal to the details necessary in a site-specific monitoring plan. Those results are presented in the DQO chapter of this proposal (Chapter 4.0).

It is recognized that vadose zone strategies at the Hanford Site are evolving and that this document will need revision to reflect new priorities and new information. Also, the conclusions and recommendations in this proposal are subject to the strategies and activities of the more broad, sitewide Groundwater/Vadose Zone Integration Project.

## **1.1 Scope**

The scope of this proposal covers all liquid and solid waste disposal facilities and unplanned releases with two exceptions. First, vadose zone monitoring that is part of the Tank Waste Remediation System (TWRS) Program is not considered by this proposal. Second, facilities and unplanned releases that currently are undergoing remediation and remediated sites that do not require post-closure vadose zone monitoring are not considered by this proposal.

The basic purpose of the monitoring described here is protection of groundwater. This is accomplished by monitoring contaminants in the vadose zone for changes in the subsurface distribution of those contaminants or for changes in soil characteristics that could lead to changes in contaminant distribution. Any changes in subsurface contamination are to be evaluated for impacts on groundwater. Characterization activities are not part of the scope covered by this proposal, although the vadose zone monitoring project may recommend site-specific characterization activities to establish a baseline against which to monitor. Where needed, the vadose zone monitoring project may make recommendations for types, sizes, and depths of monitoring points and monitoring networks to be protective of groundwater.

## **1.2 Document Organization**

This document consists of four parts. The main part provides guidance for subsequent site-specific vadose zone monitoring plans and includes 1) background information consisting of a brief description of the Hanford Site vadose zone geology and existing monitoring data, 2) a description of the results of the DQO process used for this proposal, 3) a prioritization of waste sites that need vadose zone monitoring, and 4) a general monitoring and analysis plan.

In addition, this document contains three appendices. The first is a general quality assurance project plan (Appendix A). That appendix and portions of the main document can serve as part of site-specific monitoring plans. The second appendix (Appendix B) is a detailed description of the prioritization process used to rank liquid waste disposal facilities for vadose zone monitoring. That appendix will be updated as new information is available. The third appendix (Appendix C) will contain site-specific information for those sites to be monitored during the upcoming fiscal year. The appendix will contain site-specific maps, inventories, constituents of concern, results of previous monitoring, existing subsurface access, existing contamination, applicable regulatory limits, and monitoring frequencies. Appendix C will be updated as necessary to support annual vadose zone monitoring activities.

**THIS PAGE INTENTIONALLY  
LEFT BLANK**



## **2.0 Vadose Zone Geology**

The stratigraphy of the Hanford Site consists of the Columbia River Basalt Group overlain by the Ringold Formation, Hanford formation, and Holocene fluvial and eolian deposits (Figure 2.1). The vadose zone consists of the upper portion of the Ringold Formation, the Hanford formation, local units such as the Plio-Pleistocene unit, and Holocene deposits.

### **2.1 Ringold Formation**

The Ringold Formation is a heterogeneous mix of variably cemented and compacted gravel, sand, silt, and clay. These strata record a history of alluvial and lacustrine sedimentation and pedogenic activity associated with the ancestral Columbia River system between 8.5 and 3.4 million years ago (Fecht et al. 1987). Braided streams and lacustrine settings dominated the depositional environment. Ringold Formation deposits on the Hanford Site represent an eastward shift of the Columbia River from the west side of the site to the east side.

Lindsey (1996) described the Ringold Formation in terms of five facies, consisting of fluvial gravels, fluvial sands, overbank-paleosol deposits, lacustrine deposits, and basaltic alluvium. Using these facies, Lindsey (1996) then divided the Ringold Formation into three informal members: Wooded Island, containing five separate intervals designated units A, B, C, D, and E; Taylor Flat; and Savage Island (see Figure 2.1).

The Ringold Formation is up to 185 m thick in the deepest part of the Cold Creek syncline south of the 200 West Area. The vadose portion of the Ringold Formation thins from east to west (approximately 16 m [50 ft] to about 13 m [40 ft]) and consists primarily of a slightly silty coarse- to medium-grained sandy gravel (Ringold unit E).

### **2.2 Intervening Plio-Pleistocene Unit, Pre-Missoula Gravels, and Early "Palouse" Soil**

Locally, the Ringold Formation and overlying Hanford formation are separated by informally defined, discontinuous late Pliocene to early Pleistocene deposits.

The Plio-Pleistocene unit unconformably overlies the Ringold Formation in the western Cold Creek syncline near the 200 West Area. The unit is up to 25 m (82 ft) thick and consists of basaltic gravels and pedogenic calcrete (Delaney et al. 1991). The eastern edge of the gravel facies occurs along the southwest boundary of the 200 West Area. The Plio-Pleistocene unit appears to be correlative to other sidestream alluvial and pedogenic deposits found near the base of the ridges bounding the Pasco Basin on the north, west, and south.




Figure 2.1. Suprabasalt Stratigraphy at the Hanford Site

The pre-Missoula gravels consist of quartzose to gneissic clast-supported pebble to cobble gravel with a quartzo-feldspathic sand matrix (Delaney et al. 1991). These deposits underlie the Hanford formation near the 200 East Area. They are up to 25 m (82 ft) thick and are distinguished from the underlying Ringold deposits, in that they contain less basalt and have a distinctive bleached color. The nature of the contact between the pre-Missoula gravels and the Hanford formation is not well determined (Delaney et al. 1991).

The early "Palouse" soil consists of up to 20 m (65 ft) of massive and compact silt and fine-grained sand that overlies the Plio-Pleistocene unit in the western Cold Creek syncline around the 200 West Area (DOE 1988). The unit is differentiated from overlying Hanford formation deposits by greater calcium carbonate content, massive structure, and high natural gamma response in geophysical logs (DOE 1988).

## **2.3 Hanford Formation**

The Hanford formation is an informally named unit that represents all the deposits of the cataclysmic floods of the Pleistocene epoch (2 Ma to 13 ka). The floods came from glacial Lake Missoula, Lake Bonneville, and other ice margin lakes associated with continental glaciers that spread south as far as the present Columbia Plateau. Glaciers damming the lakes may have given way as many as 40 times during late Wisconsin time, allowing impounded water to spread across eastern Washington and form the Channeled Scablands. These flood waters collected in the Pasco Basin and formed Lake Lewis, which slowly drained through the small water gap in the Horse Heaven Hills called Wallula Gap.

Three principal types of deposits were left behind by the Lake Missoula floods: 1) high-energy deposits consisting of gravel; 2) low-energy, slackwater deposits consisting of rhythmically bedded silt and sand, known as the Touchet Beds; and 3) coarse to fine sand deposits representing an energy transition environment. The Hanford formation typically has been divided into a variety of sediment types, facies, or lithologic packages. Recent reports dealing with the Hanford formation (e.g., Delaney et al. 1991, Reidel et al. 1992) have recognized three basic lithofacies: 1) gravel dominated, 2) sand dominated, and 3) silt dominated. These facies generally correspond to the high-energy, coarse gravels, the transitional laminated sands, and the lower energy, graded rhythmites, respectively (DOE 1988, Baker et al. 1991, Delaney et al. 1991).

Gravel-dominated strata consist of coarse-grained sand and granule to boulder size gravel that display massive bedding, plane to low-angle bedding, and large-scale cross-bedding in outcrop. Matrix commonly is lacking from the gravels, giving them an open-framework texture. The sand-dominated facies consists of fine- to coarse-grained sand and granules that display plane lamination and bedding and, less commonly, ripple lamination and plane and trough cross-bedding. Small pebbles and pebbly interbeds (<20 cm [8 in.] thick) may be encountered in the sand-dominated facies. The silt content of these sands varies, although where it is low, an open-framework texture may occur. The silt-dominated facies consists of silt and fine- to coarse-grained sand forming normally graded rhythmites. Plane lamination and ripple cross-lamination are common in outcrop.

## **2.4 Holocene Deposits**

Holocene surficial deposits consisting of silt, sand, and gravel form a thin (<5-m [16-ft]) veneer across much of the Hanford Site. These deposits resulted from recent fluvial processes along the Columbia River and sidestream channels and from eolian processes in the central part of the Hanford Site.

## **2.5 Discontinuities**

Discontinuities in the vadose zone sediments can serve as preferential pathways or as barriers to liquids reaching groundwater. The major discontinuities are clastic dikes, faults, fractures and joints.

Clastic dikes are a common geologic feature in the suprabasalt sediments at the Hanford Site. Clastic dikes are generally vertical to subvertical sedimentary structures that cut across normal sedimentary layering. They are most common in the Hanford formation but also have been identified in the Ringold Formation, the Ellensburg Formation, and the Columbia River basalts. Clastic dikes exhibit a wide variation in their dimensions, internal structure, infilling material, and relationships with one another. The most important feature of clastic dikes is their potential to either enhance or inhibit (depending on textural relationships) vertical and lateral movement of contaminants in the subsurface. Black (1979) and Fecht et al. (1998) have compiled most of the information known about clastic dikes in the Pasco Basin.

Faults, fractures, and joints are structural discontinuities that can provide potential vertical pathways to groundwater. These features are most common in competent rock near anticlinal ridges but are not confined to only those areas. Faults have been observed throughout the Pasco Basin but are typically sparse away from the major anticlines. Joints and fractures differ from faults, in that there is little to no relative movement on either side of the fractures. They are very common wherever competent, brittle, deforming rock has undergone folding as in the Pasco Basin. Fractures and joints typically break the cemented rock of the Ringold Formation and caliche layers of the Plio-Pleistocene unit. The uncemented Hanford formation and ductile clay-rich beds of the Plio-Pleistocene unit are probably less susceptible to joints and fractures. However, shrinkage of clay-rich beds as they dry out will produce abundant joints and fractures.

## 3.0 Past Vadose Zone Monitoring at Hanford

Traditionally, at the Hanford Site, vadose zone monitoring has consisted primarily of borehole geophysical logging using a gamma-ray sonde. The earliest logging was gross gamma-ray logging. Spectral gamma-ray logging has been used at the site since the late 1970s. Other, but less-often used, tools included neutron probes for moisture content, temperature probes for tracking the heat of radionuclide decay, and copper foils for alpha tracking. This chapter describes the historical monitoring that has been done with particular emphasis on results that have been published and are available to serve as a baseline for future vadose zone monitoring.

### 3.1 Gross Gamma-Ray Logging

Scintillation well logging started at the Hanford Site in the late 1940s to assess the performance of waste disposal facilities. The earliest, published scintillation probe studies were conducted in 1964 and 1969 to evaluate the distribution, redistribution, and decay of radionuclides discharged to the ground from crib facilities. The studies were based on scintillation probe profiles developed from crib monitoring, well-logging operations between 1954 and 1968. The 1964 study (Raymond and McGhan 1964) discusses the disposition of radionuclides beneath most of the crib facilities in use up to 1963, whereas the later study (Tillson and McGhan 1969) discusses only those crib facilities where changes or lack of changes in the scintillation profiles through 1968 were considered significant (Fecht et al. 1977).

Fecht et al. (1977) report gross gamma-ray monitoring results from about 300 wells adjacent to approximately 100 crib facilities. Their purpose was to qualitatively measure the distribution of radionuclides beneath the facilities. They published the resulting scintillation profiles and compared those profiles to previous measurements. Additon et al. (1978a, 1978b) produced an updated catalogue of available scintillation profiles but included no interpretation of the data.

Most of the scintillation logs collected for the above studies were collected with the "third generation" logging system. The system sonde consisted of a 7-cm diameter stainless steel container housing a preamplifier and a 5.1-cm by 5.1-cm NaI(Tl) crystal coupled to a photomultiplier tube. The equipment was not calibrated to today's standards but some calibration was done. Fecht et al. (1977) report that the system had a low detection limit of about 3 pCi ( $^{106}\text{Ru}$ - $^{106}\text{Rh}$ )/mL in water and about  $3 \times 10^4$  millirems ( $^{226}\text{Ra}$ )/hr in air. The maximum meter count rate in air was 1,000,000 counts/min in a field of about 150 mr/hr. Maximum meter count rate in water occurred at a  $^{106}\text{Ru}$ - $^{106}\text{Rh}$  concentration of about 5,000 pCi/ml (Fecht et al. 1977).

### **3.2 Spectral Gamma-Ray Logging**

Since about 1990, approximately 450 Hanford Site boreholes have been logged with the radionuclide logging system. That system was based on, but highly modified from, its predecessors, the mobile radiation analytical laboratory II and Devan II which had been used at tank T-106 and other sites. The radionuclide logging system uses logging tools with NaI and intrinsic germanium gamma-ray detectors. This system, its associated software for quantitative analysis, and calibration facilities brought a degree of quantitiveness not found in the earlier logs.

Many, but not all, of the results of spectral gamma logging with the radionuclide logging system have been reported in topical publications, characterization studies, and unpublished letter reports. All spectral gamma log data collected since 1990 have been cataloged into a database that is available through the Hanford Groundwater Monitoring Project on the Pacific Northwest National Laboratory server at \\pnlatlas\geodata.

### **3.3 Neutron Logging**

A neutron soil moisture logging system was designed and fabricated in 1963 to delineate subsurface wetted zones adjacent to liquid waste disposal sites and for use in stratigraphic studies (Sheen et al. 1964). A well (699-11-45A) was drilled and cored specifically for calibration of the neutron probe. Core samples were analyzed for water content, and the well was logged with the neutron probe to relate probe response to water content of the subsurface geologic media. The neutron logging system was extremely sensitive and easily detected a fraction of a percent change in moisture content. Use of the neutron probe was discontinued when more stringent radiation protection measures were implemented that made it difficult to shield operating personnel from the Pu-Be source radiation (this information was obtained from a 1992 letter report by J. R. Raymond and V. L. McGhan, Pacific Northwest Laboratory). Much of the early neutron logs exist in files, but they have not been collected into a database or a comprehensive catalogue. No interpretation or compilation of early neutron logs has been published.

In 1995, Westinghouse Hanford Company adapted a commercially available moisture tool for use in vadose zone logging at the Hanford Site. Since that time, nearly 50 wells have been logged but most of the data have not been published. Moisture calibration models were constructed in 1994 under a Cooperative Research and Development Agreement (Engelman et al. 1995) and the models currently are available for use.

### **3.4 Compilations of Logging Data**

Several compilations of borehole geophysical logs have been published over the years. These reports did not produce any new data nor accumulate existing data but did enumerate what data exist and referenced sources for their retrieval.

The first such report was by Blair et al. (1981). They cataloged the existing borehole geophysical data collected from about 800 wells between 1954 and 1980. Their report associates the type of log (gamma-gamma, neutron-gamma, neutron epithermal neutron, natural gamma, caliper, and sonic) with the date collected and source well.

Lewis and Pearson (1992) compiled a listing of over 1,000 geophysical logs obtained from over 250 monitoring wells in the 100 Areas and adjacent 600 Area. They list, among other things, the type of log, the date collected, the well logged, and the physical location of the log.

Eight similar compilations were made in 1991 and 1992 as part of geologic data packages in support of the Aggregate Area Management Studies. One compilation was made for each of B Plant (Teel et al. 1992), C Plant (Chamness et al. 1992a), Plutonium-Uranium Extraction Plant (Chamness et al. 1992b), S Plant (Teel 1992), T Plant (Chamness et al. 1991a), U Plant (Chamness et al. 1991b), Z Plant (Chamness et al. 1991c), and 200 North Area (Chamness et al. 1992c).

### **3.5 Other Characterization and Monitoring Data Sources**

Several special studies have been done over the years at the Hanford Site that produced data and information that may be a suitable baseline for certain types of vadose zone monitoring.

Over 2,900 wells were constructed on the Hanford Site by 1985 (McGhan et al. 1985). Nearly all of these wells were installed to provide a means for monitoring the waste disposal sites both within the vadose zone and within the uppermost aquifer. Under waste management programs at the Hanford Site, numerous waste disposal facilities (including cribs, trenches, french drains, reverse wells, ponds, ditches, and burial grounds) were characterized beginning in the 1950s. Most of these characterizations were primarily limited to the measurement of radionuclide distributions in the sediments around the facilities. Documentation of these studies exists primarily in topical reports and letter reports by Hanford Site contractors. It is beyond the scope of this document to compile and annotate each of those characterization efforts. As monitoring tasks are implemented, site-specific monitoring plans will be written, and those plans will describe existing characterization data appropriate to compare with newly acquired monitoring data.

### **3.6 Uses of Historical Data for Current and Future Monitoring**

The major use of historical information for vadose zone monitoring is as baseline information against which to compare new information. It is recognized that the details of some older data are unknown and that some older data were not collected in a manner that could meet today's quality control standards. Nevertheless, much of the older data, when properly qualified, is useful for comparisons with new information to determine changes in subsurface contaminant distribution.

**THIS PAGE INTENTIONALLY  
LEFT BLANK**



## **4.0 Data Quality Objectives Process**

### **4.1 Introduction**

This chapter addresses the relevant components of the general DQO process (EPA 1994) as they apply to vadose zone monitoring at the Hanford Site. This chapter describes the outcome of the DQO process as it was applied to vadose zone monitoring. The authors of this proposal met with key individuals who have been involved with vadose zone activities across the Hanford Site. These individuals were asked to discuss the vadose zone and their perspective on what should or should not be done, why it should or should not be done, and how it should be done. The individuals included geoscientists from the Environmental Restoration Contractor, the Prime Hanford Management Contractor, and the Research and Development Contractor, representing a wide variety of projects including the Groundwater/Vadose Zone Integration Project and the Tank Waste Remediation Systems Project, to obtain a wide range of perspectives. Each participant had an opportunity to review this proposal during its preparation.

### **4.2 Description of DQO Process and Limitations**

The DQOs ensure that the type, quantity, and quality of environmental data used in the decision-making process are appropriate for their intended applications. The process for developing DQOs involves seven steps:

- statement of problem (Section 4.4)
- decision and expected action (Section 4.5)
- decision inputs (Section 4.6)
- study boundaries (Section 4.7)
- decision rule (Section 4.8)
- limits on decision errors (Section 4.9)
- optimize sampling design (Section 4.10).

The DQO process has both quantitative and qualitative aspects. The quantitative aspect seeks to use statistics to design the most efficient field investigation that minimizes the possibility of making an incorrect decision. The qualitative aspect seeks to encourage good planning for field investigations and complements the statistical design. The DQO process is designed to be both flexible and iterative.

This vadose zone monitoring proposal specifies the type, quantity, and quality of data needed to support decisions related to monitoring the vadose zone at hazardous waste sites.

### 4.3 Data Requirements and Regulatory Drivers

The principal driver for monitoring the vadose zone is protection of groundwater. Although there are no regulations requiring vadose zone monitoring, such monitoring is being considered as an alternative or an extension of groundwater monitoring for at least one RCRA-regulated facility, the Liquid Effluent Retention Facility. Declining water levels beneath this facility will soon render the current groundwater monitoring network noncompliant with established groundwater protection standards (40 CFR 265, WAC 173-303-645). Although neither the U.S. Environmental Protection Agency (EPA) nor the State of Washington Department of Ecology (Ecology) has promulgated regulations relative to RCRA vadose zone monitoring, DOE and Ecology have proposed vadose zone monitoring activities for the Hanford Site. An alternative monitoring strategy is necessary to maintain RCRA compliance at the Liquid Effluent Retention Facility, and vadose zone monitoring is considered to be one component of the strategy.

DOE Order 5400.1 specifies an environmental surveillance program designed to monitor the effects of DOE activities on onsite and offsite environmental and natural resources. At the Hanford Site, effluent monitoring and near-facility surface and groundwater monitoring have been established to accomplish the goals of DOE Order 5400.1. Vadose zone monitoring is one of the approaches to augment near-facility and groundwater monitoring.

The DQO process participants concluded that, in spite of the absence of any regulatory driver for monitoring the vadose zone, such monitoring is in the best interests of the DOE and the public because it represented the *best management practice* for the Hanford Site. Most of the waste disposed to the vadose zone remains in the vadose zone, and most groundwater plumes originated from waste in the vadose zone. Once waste has reached the groundwater, the difficulty and expense of cleaning it up greatly increases. Thus, monitoring the vadose zone contributes to an early warning system that can head off potentially expensive groundwater remediation.

### 4.4 Statement of Problem

The overall goal of vadose zone monitoring is protection of groundwater through monitoring changes in subsurface contaminants. Vadose zone monitoring provides an early warning system with respect to hazardous material moving through the vadose zone to the groundwater. Early detection can save money on expensive corrective actions and protect natural resources. Periodic measurement of the concentration and distribution of vadose zone contaminants accomplish this goal.

To develop the DQOs that adequately address vadose zone monitoring data needs, the overall performance objective or goal must be identified. One objective of monitoring is to support the Hanford Groundwater Monitoring Project by providing information on contaminant movement in the vadose zone before it reaches the water table. A second objective is to collect data that can be used to demonstrate that radiological and hazardous contaminants will or will not exceed applicable groundwater standards (e.g., WAC 246-290, WAC 173-200, 40 CFR 141, 40 CFR 143, DOE Order 5400.5) or that contaminants will or will not cause unacceptable health risks (e.g.,  $>10^{-4}$ ). The first objective is the primary objective of this

proposal. The second objective requires an assessment of the amount and rate of movement of contaminants through the vadose zone and their impact on the groundwater. This assessment is beyond the scope of this proposal but vadose zone monitoring as described in this proposal is designed to collect data that can support both of these objectives.

As discussed above, there are no applicable regulatory standards for vadose zone monitoring. Therefore, the problem that vadose zone monitoring should address is:

**Will contamination in the vadose zone migrate to the groundwater and result in the exceedance of applicable groundwater standards or pose an unacceptable risk to human health or the environment?**

#### **4.4.1 Conceptual Model Considerations**

Part of the first step in the DQO process is the development of a conceptual model of the processes to ensure that the type, quantity, and quality of monitoring data to be collected are appropriate for the intended use.

The principal element of a vadose zone model of the Hanford Site is the stratigraphy (see Chapter 2.0). The stratigraphic units of the vadose zone form a series of nearly horizontal layers across the site. The horizontal layering is locally cut by clastic dikes and by joints in the more competent units. Clastic dikes are vertical to subvertical sedimentary structures that cut across normal sedimentary layering. Both of these features have the potential to provide preferential pathways to the water table. In addition, poor borehole construction from past installations also may provide conduits to the water table. Finally, and although not directly related to the vadose zone stratigraphy, the high salt content of some disposed waste can also lead to preferential flow, or fingering, through the vadose zone.

Because of the limited information available for the subsurface, there is a great uncertainty associated with the conceptual model. Boreholes are the main source of information followed by limited geophysical data. Some sites have just a few boreholes while others have higher degrees of characterization. Thus, the uncertainty will vary from site to site and cannot be generalized for the Hanford Site vadose zone.

In the past, contaminants were directly discharged to the vadose zone with the intent that they would be immobilized due to the sorption properties of the soil. The capacity of the discharge areas varied, and some sites received more waste than could be captured by the soil column. In sites that exceeded their capacity, the more mobile constituents reached the water table, producing the present groundwater plumes. At the low-volume sites, where much less effluent was discharged, the mobile constituents have been retained in the soil column and are only slowly draining to the water table under either natural or artificial recharge conditions.

The important factors in this conceptual model were brought out during the DQO process and include: 1) the constituents disposed to the soil column, 2) the migration or exposure pathways, and 3) the driving force. Any combination of unfavorable factors could result in contaminants migrating to

the water table and producing or adding to a groundwater plume. Therefore, the conceptual model that this DQO process addresses is one where the mobile and hazardous contaminants that were disposed to the vadose zone are migrating to the water table. The driving force is either natural or artificial recharge.

#### **4.4.2 Resource Constraints**

At this time, the principal resource constraints are 1) the lack of proven technologies to detect some of the constituents of interest in the soil or to detect them at the required level of detection, 2) budget constraints, and 3) lack of a baseline for some sites.

### **4.5 Decision and Expected Action**

The second step in the DQO process is to identify the key decisions that will be made with the monitoring data and any alternative actions that may be taken based on the findings of the monitoring program. The first decision to be made is:

**Is there a need to monitor the vadose zone at a specific site?**

The relevant decision that will be made using the vadose zone monitoring data is:

**Are contaminants migrating through the vadose zone and likely to reach the water table and exceed applicable drinking water standards, other applicable environmental standards, or pose unacceptable environmental risks?**

The actions that may be taken depend on the answer to this question. If there is no impact, then no action is required. If there is an impact, then the action to be taken at a site depends on the level of the impact and the status of the site.

### **4.6 Decision Inputs**

There are three main factors that need to be evaluated for each site to arrive at the correct answers to these questions:

#### **1. What are the constituents of concern?**

The constituents of concern that were disposed at a waste site are the most important factors to be considered for vadose zone monitoring. The vadose zone monitoring DQO process established the specific constituents of concern for the waste sites and categorized them into three groups: mobile constituents, long-lived radionuclides, and moisture (driving force).

Mobile constituents are those compounds or ions that can readily move through the soil column without being sorbed or reacting with the soil and being significantly delayed as they move downward through the vadose zone. Mobile constituents can be essentially nonreactive, complexes, or colloids. Long-lived radionuclides are those that will not decay before reaching groundwater. A working definition of a long-lived radionuclide is one that would take 20 half-lives ( $10^6$  reduction) to reach groundwater at the Darcy velocity.

Not all hazardous constituents disposed to the vadose zone are mobile or long-lived or even present in significant abundance. Under the right conditions, a relatively immobile radionuclide such as  $^{239}\text{Pu}$  could reach the water table before it has decayed and thus significantly affect the groundwater. A hazardous and mobile but low abundant constituent of concern, even if it is long lived, might not significantly affect groundwater if it does not reach the water table in high enough concentrations. Therefore, the abundance and mobility of a radiocontaminant must also be considered along with its half-life.

The DQO effort enumerated the important constituents of concern as the mobile contaminants ( $^{99}\text{Tc}$ ,  $^{129}\text{I}$ , nitrate, uranium, chromium, carbon tetrachloride, cyanide, and soluble aluminum) and the immobile and/or moderate or long-lived radionuclides (plutonium, americium, and cesium).

The DQO process brought out that some of the constituents of concern are not readily detectable using standard monitoring techniques so surrogates may need to be used. Moisture was considered a constituent of interest because moisture may serve as a surrogate for mobile contaminants and also because moisture is the driver for contaminant movement in the subsurface. Therefore, moisture was included as a constituent of interest.

## **2. What is the recharge rate?**

Artificial or natural recharge is the driving force for migration of contaminants in the vadose zone and the next most important factor after constituents of concern. The amount of recharge is site dependent. Natural infiltration affects all waste sites but the infiltration rates are greater where vegetation is lacking, no cover is present, or the overlying material is coarse grained. Artificial recharge historically has been the greatest source of recharge and can come from a variety of sources, including other waste sites, broken water lines, and runoff from natural precipitation that has been channeled or otherwise concentrated in a smaller area by surface features. Localized variations in recharge can have significant effects on the potential for constituent transport. Some sites have had many pore volumes of liquid added to the site, effectively flushing the mobile constituents down to the water table.

## **3. What are the flow paths through the vadose zone?**

The dominant flow path through the vadose zone is the most difficult factor to quantify. The conceptual model for the vadose zone is one of horizontal layering with features such as clastic dikes or poorly constructed boreholes that might provide conduits to the water table. Horizontal layering will cause lateral spreading as it impedes downward movement of moisture; perched water is not uncommon at the Hanford Site. If these layers become saturated, then horizontal layering can have little effect on slowing

downward migration. The principal flow path for a site will be dependent on a combination of these factors and thus will be difficult to predict without detailed characterization.

## 4.7 Study Boundaries

This section identifies the spatial and temporal domain boundaries needed to address the decision rules. This step in the DQO process defines the set of boundaries covered by the decision(s) being put forth.

- *Spatial Boundaries.* The spatial boundaries for vadose zone monitoring should include the actual disposal site plus the area that could be impacted by migration from the disposal site. The area impacted is that area where lateral spreading could occur. At present, there are established regulatory compliance boundaries only for RCRA-regulated sites. Most past liquid waste disposal sites are not covered under RCRA and, therefore, have no established regulatory boundaries.

The disposal site boundaries are well defined, but it is difficult to estimate the extent of lateral spreading. Characterization activities should define the extent of lateral spreading but the characteristics of each waste site will need to be considered in establishing the specific spatial limits of a site.

- *Temporal Boundaries.* The temporal boundary includes how often is it necessary to monitor and how long monitoring should be done. Infiltration rates are probably the dominant factor controlling the rate of contaminant migration. Unless a waste disposal site is an active site or near a site that is receiving effluent (e.g., B Pond), downward migration could be assumed to be slow because natural recharge is low. Thus, infiltration rates can be used as a method for estimating the relative frequency needed for monitoring. The presence of long-lived constituents will be the controlling factor for how long it will be necessary to monitor a site.

The current status of a waste site is also a factor in defining temporal boundaries. All else being equal, inactive waste sites require less-frequent monitoring than active waste sites. Finally, sites with signs of recent contaminant movement should require more frequent monitoring than sites with a history of no contaminant movement.

## 4.8 Decision Rule

As described in the DQO guidance manuals (EPA 1994), this step integrates previous steps into a statement that describes the logical basis for choosing among alternate actions. This involves specifying the 1) constituents of interest, 2) need for monitoring at a site and the site's priority level, and 3) monitoring methods that could be employed. These elements are then combined into "if-then" statements that can be used for developing the decision rules that can then be applied for determining if a site needs to be monitored, its priority, and the appropriate monitoring techniques.

1. Is there a current threat imposed by site conditions on the environment? Are there known or suspected factors or conditions that would lead one to believe that the site is or could impact groundwater? If there is a current threat to the environment by the site, then the site should be given a higher priority for vadose zone monitoring.
2. Is there a regulatory reason to monitor? Are there applicable laws or regulations that require a site to be monitored? If there is no regulatory reason to monitor, then the site should be given a lower priority for monitoring.
3. Are there mobile contaminants at the site? If there are mobile contaminants at the site, then the site should receive a higher priority for monitoring.
4. Are there long-lived contaminants associated with the site? Are there constituents at the site that, even in small quantities, are so long lived that they could provide hazardous conditions in the future? If there are long-lived radionuclides, then the site should be given a higher priority for (but perhaps less frequent) monitoring.
5. Have mobile constituents been “flushed” from the vadose zone? Has the site received so much liquid that mobile constituents could have been completely removed from the soil column and flushed into the groundwater? Did past-practice activities dispose high volumes of liquid that could have remobilized the hazardous or radioactive waste and removed it from the soil column? If the site has had several pore volumes of liquid put through it that contained no hazardous, mobile, or long-lived compounds, then mobile constituents may have been flushed from the site and there may be no reason to monitor the vadose zone. If, however, immobile and long-lived contaminants were disposed to the site, they may not have been flushed and vadose zone monitoring may be appropriate. If the site has been flushed of contaminants, then the site should be given a lower priority for monitoring.
6. Is there a potential for future impact to groundwater? Are there known conditions such as high recharge that would lead one to suspect that the site could impact groundwater in the future? If there are conditions that would likely exceed a groundwater limit, then the site should receive a higher priority for monitoring.
7. Are there vadose zone plumes associated with the sites? Has past monitoring or baseline characterization shown that there is a known vadose zone plume at the site? If there is a known vadose zone plume at the site and if the magnitude of contamination could cause groundwater to exceed regulatory limits, then the vadose zone at the site should receive a higher priority for monitoring.
8. Is there a current impact to groundwater at a site? Is there a known groundwater contamination plume emanating from the site, and is it above some applicable standard? If there is a current impact on groundwater at the site, then contaminants at the site are migrating into the groundwater and vadose zone monitoring cannot be used as an early warning system for groundwater contamination. However, vadose zone monitoring still can provide information on the rate of migration and how long the site may continue to impact the environment. If the site has already affected groundwater, then monitoring the site should receive a lower priority.

9. Is the site in an area currently receiving liquid effluent? Are facilities currently discharging hazardous or radioactive waste to the soil at the site? If the site is currently receiving liquid effluent, then the site should receive a higher priority for monitoring.
10. Are there driving forces external to the site? Is the site in an area where some conditions such as a nearby waste site that could result in driving mobile contaminants to the water table? If there are external driving forces, then the site should be given a higher priority for monitoring.
11. Are characterization and/or baseline data available? Has the site been adequately characterized so that potential pathways and soil conditions are known? Has a baseline survey been done at the site so that future monitoring can be compared to it? If a baseline exists, then the site should be given a higher priority. If no baseline or characterization data are available but if a baseline can be established using monitoring tools, then the site should be given a higher priority. The baseline for these latter sites will consist of the first in a temporal line of monitoring events. If no baseline or characterization data are available and available monitoring methods cannot establish a baseline, then the site should be given a lower priority for monitoring and recommendations should be made to complete a baseline survey and site characterization.

#### **4.8.1 Statistical Parameters of Interest**

The statistical term “population” refers to the total collection of objects or media to be studied and from which a sample is to be drawn. For the vadose zone, the population is the contaminant plume in the vadose zone. The principal parameter to be measured is the change in concentration of constituents of concern at any point in the vadose zone. The principal problem is how to obtain a measurement of that parameter in the subsurface in an efficient and cost-effective manner and is that measurement appropriate for statistical analysis.

For groundwater monitoring, appropriate statistical analysis is prescribed in the regulations. For vadose zone monitoring, analogous regulations do not exist so that the appropriate statistical analysis for vadose zone monitoring is that which adds to answering the question “Will contaminants in the vadose zone adversely impact groundwater?” Table 4.1 lists the principal conceptual model elements and the statistical parameters of interest used to evaluate whether contaminants in the vadose zone will adversely impact groundwater.

There are several ways to obtain information from the subsurface. Boreholes are a common method of taking subsurface measurements. Either new boreholes can be drilled and samples collected and analyzed or existing boreholes can be used and estimates of constituents of concern measured using some appropriate techniques. In addition, nonborehole techniques such as lysimeters, excitation of mass, or surface geophysical methods can be used to locate moisture zones in the soil. Each technique has its own requirements and constraints, and each method has different ways of obtaining the principal parameter. In addition, each has its own cost associated with obtaining data using that method, and the DQO process is designed to take into account the cost of obtaining information.



**Table 4.1. Conceptual Model Parameters of Interest**

Conceptual Model Element	Property or Parameter	Constituents of Interest	Sampled Population	Statistical Parameters
Constituents Disposed to Soil Column	Half-life, mobility	<sup>99</sup> Tc, <sup>129</sup> I, NO <sub>3</sub> <sup>-</sup> , U, Cr, CCl <sub>4</sub> , CN <sup>-</sup> , Al, <sup>241</sup> Am, <sup>137</sup> Cs, <sup>239,240</sup> Pu	Boreholes	Central tendency
Driving Force	Long-term recharge rate	Water (moisture)	Lysimeters, tensiometers, environmental tracers, other	Central tendency
	Contemporary recharge rate	Water (moisture)	Lysimeters, tensiometers, environmental tracers, other	Central tendency
Pathways	Site characterization	NA	NA	NA
NA = Not applicable.				

#### 4.8.2 Action Level or Measurement Threshold

This element is generally taken as a cleanup standard or other regulatory standard. Because there is no regulatory standard, the action level will be taken as the point where it can be conclusively demonstrated that contaminants from the vadose zone will impact the groundwater in such a way that an applicable groundwater standard may be exceeded.

#### 4.8.3 Alternative Actions

Exceedance of the performance standard may require that some action be taken. The action may be remediation of the site, an alternative to remediation such as construction of a barrier over the site to decrease recharge, repair or maintenance of a leaking source that is impacting the site, maintenance of the site, or no action. The choice and implementation of alternative actions involving remediation are beyond the scope of this proposal but the decisions fall out of the "if-then" statements at the beginning of this section. A tentative "if-then" statement for alternative actions is:

**If waste from the vadose zone beneath a site is impacting, or will impact, the groundwater, then monitoring should continue pending use of some engineering methodology to decrease or stop the driving force for the contamination or remove the source of contamination.**

#### 4.9 Limits on Decision Errors

This step of the DQO process specifies the limits on decision errors that are deemed tolerable. Errors related to input data acquisition consist of both sampling and measurement components. The combination of these errors is the *total study error*, which is directly related to the decision error.

A decision error occurs when the data lead the decision maker(s) to believe 1) the null hypothesis is false when it is actually true (a false-positive) or 2) the null hypothesis is true when it is actually false (a false-negative). To reduce such errors, an adequate estimate of key population parameters is needed. Reducing such error generally involves greater cost for sample collection and analysis. However, reducing decision error at an increased cost may or may not be the most desirable approach to take.

For site vadose zone monitoring, the statistical parameter of concern is the change in subsurface contamination as either an increase in concentration or a change in depth distribution. The main factors needing evaluation are the constituents of concern and recharge (see Table 4.1). (Flow path is a third factor needing evaluation but that is part of characterization instead of monitoring.) Obtaining values for change in constituents of concern and recharge is dependent on the method of collecting the data. Direct drilling and sampling are one approach, utilization of existing boreholes is another approach, and surface surveys are a third approach.

As stated above, the statistical parameter of concern is change. Any change in concentration of a constituent of concern at a specific point in the subsurface is determined by comparing most recent monitoring data with previously collected data. A change in concentration at sites with sufficient past monitoring to establish a baseline is considered to be an increase in concentration of 2 sigma from the baseline value. For sites without sufficient baseline data, a change in concentration is considered to exist if the most recent monitoring value differs from the previous value by more than 2 sigma errors on the measurement. For geophysical logging, this is determined from counting statistics.

Calibration issues are dependent on the specific monitoring technology used for data collection. Likewise, measurement errors are dependent on the specific monitoring technology. These errors can be considered in site-specific monitoring plans after a monitoring method is chosen for an individual site.

Errors associated with sample acquisition are dependent on the method of collecting the sample and the variation in the environment being sampled. As mentioned above, direct drilling and sampling, using existing boreholes, and surface measurements are three possible ways to obtain data. Different monitoring methods can use each of these accesses to samples. Errors associated with sampling are to be discussed in site-specific monitoring plans where specific methodologies are delineated.

## **4.10 Optimizing Sampling Design**

This final step in the DQO process is intended to develop alternative environmental sampling designs and evaluate their efficiency at providing the data for meeting the overall performance objective. The purpose is to identify the most resource-effective sampling design. Application or implementation of the DQO process described in this and previous sections and additional operational details are described in Chapter 6.0 and in the respective site-specific sampling and analysis plans.

As indicated, the primary focus of the DQO process has been on obtaining measurements to determine if the constituents of concern have migrated in the subsurface. The most resource-efficient sampling design is the use of existing and readily available methodologies that require a minimum of resources for data collection and data interpretation and utilize available access to subsurface contamination (Section 6.1.4.1.1 gives a discussion of the potential limitation on the use of existing boreholes).

## 4.11 Site-Specific Vadose Zone Monitoring Strategy

Table 4.2 summarizes the major elements of the strategy behind the development of site-specific vadose zone monitoring. It is recognized that the strategy for vadose zone monitoring at the Hanford Site is evolving, and elements in this proposal will need to follow that evolution. However, Table 4.2 provides the overall process that is necessary to develop site-specific monitoring. The following chapters elaborate on the elements in the table and provide the rationale for prioritizing waste sites, selecting the constituents of concern, and selecting monitoring methods.

**Table 4.2. Elements of Vadose Zone Monitoring**

Vadose Zone Monitoring Component	Element	Requirement or Procedure	Documentation
Assessment of liquid effluent disposal facilities	List of prioritized facilities	DQO process	This proposal
	Define data needs		
Site-specific vadose zone monitoring plans	Conceptual model		Site-specific plan
	Identify site-specific data needs		
	Evaluate site-specific data		
	Develop vadose zone monitoring network		
Site-specific monitoring	Sampling and analysis plan	Best management practice	
	Procure data collection services	Groundwater project quality assurance project plan	Laboratory contract, logging contracts, statements of work
	Coordinate with team members and supporting services	Best management practice	NA
	Field inspection of facilities and boreholes	Best management practice	Field inspection forms, borehole completion reports
	Data collection	Vendor-specific quality assurance project plan, vendor-specific procedures, SW 846 (EPA 1986)	Chain-of-custody, sample field records, borehole survey data sheets, calibration certificates, laboratory analytical records, analytical data sheets
	Quality control	Vendor-specific procedures, vendor-specific quality assurance project plan, groundwater project quality assurance project plan	Chain-of-custody, sample field records, borehole survey data sheets, calibration certificates, laboratory analytical records, analytical data sheets
Data analysis and interpretation	Comparison with past monitoring data	Best available technologies	Reports
Data management	Maintenance of databases	Groundwater project quality assurance project plan	Hanford Environmental Information System database, Pacific Northwest National Laboratory geophysics database
Reporting			Hanford Site groundwater monitoring reports, Hanford Site environmental reports

NA = Not applicable.

**THIS PAGE INTENTIONALLY  
LEFT BLANK**

## 5.0 Site Prioritization

This chapter briefly describes the process used to prioritize liquid and solid waste disposal sites to determine the needs for vadose zone monitoring. A more complete description of the prioritization process is given in Appendix B.

### 5.1 Prioritization Process

The DQO process led to the following criteria to be applied to determining the need for vadose zone monitoring at each waste site (see Section 4.8).

1. Is there a current threat imposed by site conditions on the environment?
2. Is there a regulatory reason to monitor?
3. Are there mobile contaminants associated with the site?
4. Are there long-lived constituents associated with the site?
5. Have mobile constituents been "flushed" from the vadose zone?
6. Is there a potential for future impact to groundwater?
7. Are there vadose zone plumes associated with the site?
8. Is there a current impact to groundwater at the site?
9. Is the site in an area currently receiving liquid effluent?
10. Are there driving forces external to the site?
11. Are characterization and/or baseline data available?

These criteria were applied to each waste site in the 200 Areas. The *Waste Site Grouping for 200 Areas Soil Investigations* (DOE 1997b) was used as a preprioritized list of sites. Positive responses to the criteria included the site on the highest priority list; negative responses relegated the site to a lower priority list. Decision rules were combined when possible. Sites remaining on the lists after all 11 criteria were applied were further prioritized according to the type of facility (e.g., specific retention, crib) and how recently the site had been monitored.

Criterion 3, "Are there mobile contaminants associated with the site?" considered  $^{99}\text{Tc}$ ,  $^{129}\text{I}$ , nitrate, uranium, chromium, carbon tetrachloride, cyanide, and soluble aluminum as the mobile contaminants of concern. There were no data for aluminum available in the right format to include in this prioritization effort. Some data about aluminum inventories exist in some of the source aggregate area management study reports and those data can be included in subsequent revisions to this proposal.

### 5.2 Prioritization Results

The results of the prioritization effort are given in Appendix B (Table B.1 shows the highest priority sites). Sixty-two sites are on the high-priority list. These are the Liquid Effluent Retention Facility,

KE Basin, and sites 1) with associated constituents of concern, 2) that have not had the mobile constituents "flushed" from the soil column (sites at which 10 or less pore volumes of effluent were disposed [see Appendix B for rationale for 10 pore volumes]), and 3) that have data available to serve as baseline for monitoring.

Also in Appendix B, Table B.2 lists the priority sites that have associated constituents of concern, less than or equal to 10 pore volumes but no associated baseline information for monitoring. Table B.3 shows the intermediate priority sites that have long-lived, relatively immobile constituents of concern but received greater than 10 pore volumes.

Within each of the tables in the appendix sites are further prioritized as follows. First, the relative ranking of waste site groups has been retained from *Waste Site Grouping for 200 Areas Soil Investigations* (DOE 1997b). Then, within each waste site group, individual sites are ranked first by waste site type, second by amount of natural recharge, and third by the date that the site was last monitored. When ranking by waste site type, specific retention facilities were placed higher on the list than other sites. This essentially ranked the sites according to decreasing pore volume because effluent discharged to specific retention facilities was usually limited to 10% or less of the available pore volume between the facility and the groundwater.

## **6.0 Monitoring and Analysis**

This chapter is a general plan that describes the rationale and general procedures for data collection and data analyses to be used during vadose zone monitoring. Subsequent revisions to this document will include an appendix with site-specific maps, available subsurface access, constituents of concern, past monitoring results, and any applicable regulatory limits for each site to be monitored. Based on that information, site-specific monitoring plans will be prepared annually for those sites to be monitored during that year. Monitoring methods and monitoring frequencies will be included in the site-specific monitoring plans.

### **6.1 Vadose Zone Monitoring**

The tasks involved in vadose zone monitoring include the following:

- determination of facilities to be monitored
- selection of constituents of interest
- selection of monitoring techniques
- designation of the monitoring network
- premonitoring activities
- acquisition of monitoring data
- data handling, analysis, interpretation, and documentation
- data management
- reporting.

#### **6.1.1 Facilities to be Monitored**

Chapter 5.0 described the process and results of an initial prioritization of sites for vadose zone monitoring. Revisions to the prioritization will be required as new information becomes available, as new site priorities develop, and as remediation efforts progress.

Monitoring for carbon tetrachloride is deferred at active carbon tetrachloride remediation sites in the 200 West Area. Two remediation activities for the carbon tetrachloride expedited response action are 1) the pump-and-treat operation at the 200-ZP-1 Operable Unit and 2) the soil-vapor extraction operation at the 200-ZP-2 Operable Unit. Monitoring for carbon tetrachloride at these sites may be implemented after remediation to support postremediation evaluation and long-term monitoring.

#### **6.1.2 Select Constituents of Concern**

The constituents of concern were determined during the DQO process. They include the mobile species ( $^{99}\text{Tc}$ ,  $^{129}\text{I}$ , nitrate, chromium, carbon tetrachloride, cyanide, aluminum, and uranium) and the immobile and/or long-lived radionuclides (plutonium, americium, and cesium).

In addition, moisture was repeatedly mentioned during the DQO process and is included as a constituent of interest because it is a primary driving force for movement of contaminants in the subsurface. Also, no readily available method to monitor some of the mobile constituents of interest currently exists ( $^{99}\text{Tc}$ ,  $^{129}\text{I}$ , and nitrate, for examples). Thus, moisture movement may provide an indication of movement of the more-mobile constituents.

### 6.1.3 Select Monitoring Methods

Selection of a monitoring method depends on technical, implementation, environmental and regulatory, and economic considerations. The most important technical consideration is "Can the method detect the constituents of concern/interest at the required levels?"

As mentioned earlier, there are no regulatory standards for vadose zone monitoring. However, there are cleanup standards being used at the Hanford Site for soils. The records of decision (ROD 1995, 1996) for the 100-BC-1, 100-DR-1, 100-HR-1, 300-FF-1, and 300-FF-5 Operable Units have adapted the State of Washington Model Toxics Control Act (WAC 173-340) levels for organic and inorganic constituents of concern. For radioactive constituents of concern, both records of decision and interim regulatory guidance from the State of Washington Department of Health use levels in 40 CFR 196, a draft regulation identified in an advance notice of proposed rulemaking at 58 FR 54474. The cleanup levels from those sources for the constituents of concern identified in this proposal are given in Table 6.1.

**Table 6.1.** Compilation of Cleanup Levels from Operable Unit Records of Decision for Vadose Zone Monitoring Constituents of Concern

Constituent of Concern	Cleanup Level <sup>(a)</sup>		Source of Level <sup>(b)</sup>
	Rural Residential	Commercial/Industrial	
Cr(VI)	400 mg/kg	NA	100 Areas ROD
Cyanide	1,600 mg/kg	NA	100 Areas ROD
Nitrate	12,800 mg/kg	NA	100 Areas ROD
$^{241}\text{Am}$	31 pCi/g	210 pCi/g	WA DOH
$^{137}\text{Cs}$	6.2 pCi/g	25 pCi/g	WA DOH
$^{239}\text{Pu}$	34 pCi/g	245 pCi/g	WA DOH
$^{99}\text{Tc}$	5.7 pCi/g	41,000 pCi/g	WA DOH
$^{234}\text{U}$	160 pCi/g	1,200 pCi/g	WA DOH
$^{235}\text{U}$	26 pCi/g	100 pCi/g	WA DOH
$^{238}\text{U}$	85 pCi/g	420 pCi/g	WA DOH
(a) Values for radionuclides are those that will individually result in an annual total effective dose equivalent of 15 mrem/yr. For mixtures of radionuclides, the sum of the ratios of the actual activities to the guideline activities must be $\leq 1$ .			
(b) 100 Areas ROD = Record of Decision (1995, 1996). WA DOH = State of Washington Department of Health (1997).			
NA = Not available.			



For vadose zone monitoring designed in compliance with certain cleanup actions, the levels in Table 6.1 may be appropriate; therefore, the monitoring method chosen must have a minimum detection limit compatible with those levels.

In some instances, however, vadose zone monitoring may be directed at detection of change in subsurface contaminant distribution. For those cases, detection limits lower than those in Table 6.1 may be appropriate. The minimum detection limit of the chosen monitoring method must be compatible with the site-specific DQOs.

The availability of the method, its level of development, its complexity and reliability are also important technical considerations.

The effort to implement the monitoring method depends on the availability of the method, appropriate access to the subsurface, level of maintenance, calibration considerations, and time involved in actual monitoring.

Environmental and regulatory considerations include whether permits are required to use the method; health and safety risks during installation, monitoring, maintenance, and calibration; generation of secondary wastes during monitoring; and any environmental effects remaining after monitoring is completed.

Economic considerations include the costs of installation, maintenance, and calibration as well as the costs of monitoring and data analysis and interpretation.

Table 6.2 lists some technically, environmentally, and economically viable monitoring methods for the constituents of interest. The information listed in Table 6.2 is abstracted from Lewis and Teel (1994), from Wilson et al. (1995), and from input received during the review process of this document. Lewis and Teel (1994) evaluated 32 technologies for use in leak detection at the Hanford Site. Some of the technologies they evaluated may also be applicable to vadose zone monitoring. Table 6.2 is not an exhaustive list of potential vadose monitoring technologies nor are all technologies listed equally feasible. Selection of a specific technology for monitoring will be a function of site-specific characteristics and will be documented in site-specific monitoring plans. Regardless of the method selected, it must provide reasonable coverage, be cost effective, provide early warning of contamination or contaminant migration, and be implementable at the Hanford Site.

#### **6.1.4 Determine Monitoring Network**

##### **6.1.4.1 Monitoring Points**

Gilbert (1987), in discussing the important considerations in designing a monitoring network, states that the crucial point is defining the target population to achieve the study objectives. The statistical parameter of concern (i.e., the study objective) for vadose zone monitoring is change in contaminant concentration and distribution. Thus, the target population is defined as the vadose zone containing contamination. Monitoring, then, becomes collecting representative samples such that the suite of

**Table 6.2. Monitoring Methods Applicable to Constituents of Interest**

Constituent of Interest	Method	Comments
<b>In Situ Measurement of Constituents of Interest</b>		
Uranium, cesium, plutonium, americium	Gross gamma-ray logging	Reliable, easy, and quick to operate; ease in data analysis; limited depth of investigation (about 20-cm [8-in.] radial distance from well); detection limit between 2 and 500 pCi/g ( $^{137}\text{Cs}$ ); long history of use at Hanford; can use existing drywells; cannot distinguish among radionuclides
	Spectral gamma-ray logging	Commercially available; more complex than gross gamma-ray logging; can resolve specific radionuclides ( $^{60}\text{Co}$ , $^{137}\text{Cs}$ , $^{152,154}\text{Eu}$ , $^{235,238}\text{U}$ , $^{239,241}\text{Pu}$ , $^{233}\text{Pa}$ , $^{241}\text{Am}$ , and others); limited depth of investigation (about 20-cm [8-in.] radial distance from well); detection limit between about 0.2 and 1,000+ pCi/g ( $^{137}\text{Cs}$ ) for solid-state detector; some detectors saturate at high-count rates; can use existing dry wells
Uranium, plutonium, americium	Prompt fission neutron logging	Commercially available; limit depth of investigation (about 20-cm [8-in.] radial distance from well); lower detection limit about 1 nCi/g ( $^{239}\text{Pu}$ ); can use existing dry wells; system cannot distinguish fissionable radionuclides ( $^{233}\text{U}$ , $^{235}\text{U}$ , $^{239}\text{Pu}$ )
Carbon tetrachloride, aluminum	Pulsed-neutron logging	Commercially available with either scintillation or solid-state detectors; more difficult to operate and to process and analyze data than other methods; system can detect H, Cl, C, O, Al, Si, Ca, S, and Fe
Carbon tetrachloride	Various mass, optical, and electrochemical sensors	Emerging technologies
Water Content	Neutron-neutron logging	Commercially available; limit of investigation about 1.8 m <sup>3</sup> (4 ft <sup>3</sup> ); detection limits between about 1% and 40% H <sub>2</sub> O; can use existing steel-cased dry wells
	Electrical induction logging	Commercially available; can see up to 1.8 m (6 ft) into formation; detection limit about 5% to 100% fresh H <sub>2</sub> O; cannot operate in steel-cased boreholes
	Pulsed-neutron spectroscopy	Commercially available with either scintillation or solid-state detectors; more difficult to operate and to process and analyze data than other methods; limit of investigation between 1% and 40% H <sub>2</sub> O
	Electrical resistivity tomography	Not commercially available; detection limit unknown (requires change in moisture content); cannot use existing boreholes
	Ground-penetrating radar (including borehole)	Commercially available; surface antennae can scan large areas; detection limits are dependent on site-specific calibration; independent local measurements may be required
	Shear-wave seismic tomography	Recently commercially available; labor intensive; detection limit is 10% to 15% change in water saturation; can use existing boreholes
	Time-domain reflectometry	Recently commercially available; point measurement; detection limit 1% to 40% H <sub>2</sub> O; can use existing boreholes with modifications
	Capacitance probes	Commercially available; detection limit dependent on site-specific calibrations and access borehole configuration; small zone of influence; repeatability better than 0.005 volumetric water content; large sensitivity to small changes in water content in dry soils; cannot use existing dry wells
	Electromagnetic induction	Commercially available; quick and easy to operate; can provide estimates over large areas; does not require boreholes; can detect small variations in soil conductivity, but calibration to water content is difficult

**Table 6.2 (contd)**

Constituent of Interest	Method	Comments
Water content (contd)	Resistivity blocks	Commercially available; work poorly in coarse-grained soils; point measurement; detection limit about -1 bar to -0.1 bar; can use existing boreholes with modifications
<b>Direct Sampling and Ex Situ Analysis</b>		
All those above plus <sup>99</sup> Tc, <sup>129</sup> I, nitrate, chromium, and cyanide	Lysimeters (suction samplers)	Various samplers are commercially available; most samplers cannot be used with existing boreholes; difficulties in dry soils (effective range 0 to 60 bars of suction); requires analytical laboratory facilities
	Membrane/filter samplers (e.g., SEAMIST)	Commercially available; labor intensive; point measurements; difficulties in dry soils; can use existing boreholes with modifications; requires analytical laboratory facilities
	Core sampling	Various samplers are commercially available; labor intensive and expensive; point measurement; cannot resample same point; requires analytical laboratory facilities
Carbon tetrachloride	Active soil-gas sampling	Commercially available; labor intensive; requires laboratory facilities; can use existing boreholes with modifications
	Passive soil-gas sampling	See above (active soil-gas sampling)
<b>Measurement of Transport Parameters</b>		
Matric potential	Tensiometers (including deep/borehole tensiometers)	Commercially available; site must be fairly moist (i.e., tension <0.85 bar); can use existing boreholes with modifications
	Thermocouple psychrometers	Commercially available; applicable in very dry soils (with tensions up to 80 bars); must be individually calibrated and needs correction for diurnal temperature changes; can use existing boreholes with modifications
	Heat-dissipation sensors	Commercially available; work poorly in coarse-grained soils (effective range is 0 to 10 bars soil suction); must be individually calibrated and are susceptible to hysteresis; point measurement; can use existing boreholes with modifications
	Osmotic sensors	Commercially available
Water flux	Water balance (drainage) lysimeters	Facilities exist throughout Hanford Site; must be properly designed to avoid edge and evapotranspiration effects; provides an integrated measurement at a particular location
	Composite in situ measurements	In use at Hanford Site; flux calculated from standard measurements of water content and matric potential; requires biweekly to monthly measurements
	Flux meter	Not commercially available
SEAMIST = Science and Engineering Membrane Instrumentation and Sampling Technique.		

samples gives an accurate picture of the contaminant plume. The problem now becomes choosing a sampling scheme to collect representative samples in a space-time framework.

Several sampling strategies are discussed in guidance by the U.S. Army Corps of Engineers (1994) and Gilbert (1987). The choice of a sampling plan depends on the study objectives (change in concentration), variability in the target population (contaminant concentration and geometry), cost effectiveness, type of measurements to be made, and convenience (Gilbert 1987). Two situations exist for vadose zone

monitoring: 1) a facility is to be monitored to detect discharges that will impact the environment and 2) a facility with specific and known contamination is being monitored to determine change. A different sampling scheme is required for each of the two situations. A statistical sampling strategy probably will be most appropriate for monitoring a facility's impact on the environment. A biased or nonstatistical sampling scheme probably will be most appropriate for monitoring changes in previously defined plumes.

The rationale for a specific sampling network is site dependent, but monitoring points (e.g., well locations) should be located consistent with DQOs in the areas most vulnerable to contamination or contaminant migration. Site-specific sampling plans will describe the sampling scheme most appropriate for the specific situation given a set of constraints defined by 1) the objective of monitoring (i.e., surveillance versus plume tracking), 2) the facility design (including soil column storage properties), 3) the contaminants of concern, 4) the monitoring technique, and 5) the level of detection (uncertainty) that is acceptable.

**6.1.4.1.1 Use of Existing Boreholes.** Most liquid disposal facilities at the Hanford Site have associated monitoring wells and boreholes. Use of existing boreholes should be strongly considered, if appropriate for the objectives of the site-specific monitoring, because they are existing access to subsurface contamination and because their use can be a substantial cost savings over emplacement of new monitoring points.

If existing boreholes are to be used for monitoring, the following considerations for a fitness-for-use evaluation are pertinent:

- *The location of the borehole with respect to the facility and to existing contamination.* Most existing boreholes were located to intercept known contamination. A review of historical data will indicate which boreholes have encountered contamination in the past. Existing plume maps should be checked, and the location of boreholes relative to the plumes noted.
- *The construction and configuration of the existing boreholes.* Existing boreholes have been constructed using a variety of materials, methods, and specifications, which may or may not conform with the objectives of site-specific monitoring. If existing boreholes are to be used, well casing impacts, well seal impacts, and screen impacts must be evaluated to ensure usability of the borehole and that project-required tolerances can be met. Unknowns in the casing thickness and material and in well seal construction and material may mean large errors in monitoring results. Borehole configuration and construction information is available through the Environmental Restoration Contractor home page (<http://www.erc.rl.gov>); in databases maintained by Waste Management Federal Services, Inc., Northwest Operations, and Pacific Northwest National Laboratory; and in data compilations such as *Hanford Wells* (Chamness and Merz 1993).

#### **6.1.4.2 Monitoring Frequency**

A second aspect of the sampling design is frequency of sampling. As with the selection of monitoring points, the selection of sampling frequency will depend on the objective of monitoring, the contaminants of concern, the monitoring technique, and the acceptable level of uncertainty. For example, a

surveillance objective will require a relatively high sampling frequency; a trend-monitoring objective will require less frequent but long sequences of sampling (Gilbert 1987). Mobile contaminants will require more frequent monitoring than less-mobile, long-lived contaminants. The site-specific DQOs will dictate the sampling frequency described in the site-specific monitoring plans, and the examination of prior data should be factored into determining the frequency.

### **6.1.5 Premonitoring Activities**

Preparation activities necessary to begin a vadose zone monitoring project include the following:

- site-specific monitoring plan that provides a strong technical basis for the site-specific monitoring
- planning
- coordination with team members
- coordination with support services as addressed in the quality assurance project plan portion of this proposal (see Appendix A).
- procurement of monitoring services and equipment.

Activities in preparation for field operations are to be accomplished prior to monitoring. Activities to be considered include radiation control technologist support for generation of radiation work permits, access to radiation zones, swabbing of wells, removal of pumps and packers from wells, surveys of instrumentation as it is removed from wells or the site, and any special requirements. If existing boreholes are to be used, they must be evaluated to ensure they meet project specification. Also, if existing boreholes are to be used, coordination also must be made with projects (e.g., soil-vapor extraction) that are already using the boreholes scheduled for monitoring. Also, boreholes that have not been entered recently may need a field inspection and be swabbed for internal contamination. Finally, coordination with the facility owner or operator should occur to avoid conflicts with facility operations.

### **6.1.6 Acquire Monitoring Services**

A detailed statement of work should be prepared prior to selection of an organization to perform the monitoring. The statement of work should delineate the following:

- monitoring method to be used
- constituents of interest, including detection limits
- quality control parameters, including precision, accuracy, and frequency of quality control samples
- calibration requirements
- document control requirements
- deliverables
- quality assurance requirements

- cost and schedule constraints
- administrative contacts and controls.

Pacific Northwest National Laboratory will maintain access to organizations capable of supplying required vadose zone monitoring services for the Hanford Groundwater Monitoring Project. Potential sources of services include Hanford Site contractors and subcontractors; subcontractors designated as prequalified by Hanford Site contractors; and evaluated, independent, private industry.

The Hanford Groundwater Monitoring Project maintains contract analytical laboratory services for use. Those services will be used as needed.

#### **6.1.6.1 Monitoring Procedures**

All vadose zone monitoring will be conducted according to approved procedures. Specific technical procedures required will be designated in the statement of work but will include procedures for the following:

- data acquisition
- calibration practices and standards
- quality control and acceptance criteria
- equipment maintenance and calibration
- data reduction, verification, and reporting
- data storage and security
- document control
- administrative procedures, including personnel training, health and safety documentation, quality assurance/quality control program, change control, and control and disposition of secondary waste.

Only proven techniques with procedures adequate to control the quality of the data will be used. All software used in the acquisition of data, the reduction and analysis of data, and data interpretation will be reviewed to confirm that the software performs as expected and correctly.

## **6.1.7 Data Reduction, Data Analysis, and Data Interpretation**

### **6.1.7.1 Data Reduction**

The specifics of reducing monitoring data from initially obtained raw information (e.g., electrical pulses counted at a multichannel analyzer) are highly dependent on the specific monitoring technique and on the specific methods used by the service organization collecting the data. Most of the details concerning data reduction are not of interest because it is the resulting concentrations or activities that are used by the end user. It is important, however, that any algorithms and software used during data reduction be verified and tested to ensure that the results are accurate.

### **6.1.7.2 Data Analysis and Interpretation**

The ultimate use of vadose zone monitoring data is comparison with past monitoring data to delineate any changes in the subsurface distribution or concentration of contaminants. This is achieved through time-series analyses (i.e., comparing data for a specific contaminant at a specific location with past data for that contaminant at the same location). Past data should be adjusted to the same scale and same units as newly collected data prior to making comparisons. Detection limits and analytical errors are available for more recently acquired monitoring data. Where this information is available for past data, quantitative or semiquantitative comparisons may be possible. For much of the older data, however, quantitative comparisons probably will not be possible because associated errors, calibration information, and detection limits are generally not available. In such cases, qualitative or relative comparisons can be done.

Presentation of the results can be as graphs of depth versus concentration, maps of location versus concentration, tables of concentration values, or any other similar and applicable presentation. Where applicable, cross sections and maps should be prepared that show changes in subsurface contamination. To the extent that "good" prior data exist, the format for data presentation should complement comparison of new data to old data.

Available information that may be related to contaminant concentrations such as local geology, effluent discharge history, and chemical properties of contaminants, co-contaminants, and host soils should be used to help understand contaminant distribution and changes in contaminant distribution.

## **6.1.8 Data Management**

The data resulting from vadose zone monitoring should be assimilated in one of two ways, depending on the specific monitoring effort. First, if hard-copy data packages are available, they should contain all pertinent header sheets, work sheets, control charts, monitoring results, quality control results, data summaries, calibration information, and narratives. Hard-copy data packages should be assembled and made available to all potential data users.

Second, electronic files of all raw data, processed data, quality control data, and any other information should be collected and made available to users. Hard-copy data and/or electronic data should be placed

in appropriate databases and libraries for use. The original data or copies of the data will be managed according to Pacific Northwest National Laboratory data management procedures (see Appendix A).

#### **6.1.9 Reporting**

The results of vadose zone monitoring should be made available for Hanford Site use. Mechanisms include publication in topical reports and in the annual Hanford Site groundwater monitoring report. All reporting will be peer reviewed. Topical reports will be issued according to Pacific Northwest National Laboratory procedures for information release, which ensures technical review. The annual groundwater report also utilizes the Pacific Northwest National Laboratory information release system and undergoes extensive technical, peer review.



## 7.0 References

40 CFR 141, Code of Federal Regulations, Title 40, Part 141. *National Primary Drinking Water Regulations*.

40 CFR 143, Code of Federal Regulations, Title 40, Part 143. *National Secondary Drinking Water Regulations*.

40 CFR 196, Code of Federal Regulations, Title 40, Part 196. *Radiation Site Cleanup Standards*. Federal Register, vol. 58, no. 202, October 21, 1993.

40 CFR 265, Code of Federal Regulations, Title 40, Part 265. *Interim Status Standards for Owners and Operators of Hazardous Waste Treatment, Storage, and Disposal Facilities*.

Additon, M. K., K. R. Fecht, T. L. Jones, and G. V. Last. 1978a. *Scintillation Probe Profiles, 200 East Area Crib Monitoring Wells*. RHO-LD-28, Rockwell Hanford Operations, Richland, Washington.

Additon, M. K., K. R. Fecht, T. L. Jones, and G. V. Last. 1978b. *Scintillation Probe Profiles, 200 West Area Crib Monitoring Wells*. RHO-LD-29, Rockwell Hanford Operations, Richland, Washington.

Baker, V. R., B. N. Bjornstad, A. J. Busacca, K. R. Fecht, E. P. Kiver, U. L. Moody, J. G. Rigby, D. F. Stradling, and A. M. Tallman. 1991. "Chapter 8, Quaternary Geology of the Columbia Plateau." In Morrison, R. B. (ed.) *The Geology of North America, Vol. K-2, Quaternary Nonglacial Geology, Conterminous U.S.*, The Geological Society of America, Boulder, Colorado.

Black, R. F. 1979. *Clastic Dikes of the Pasco Basin, Southeastern Washington*. RHO-BWI-C-64, Rockwell Hanford Operations, Richland, Washington.

Blair, S. C., L. S. Law, and J. W. Lindberg. 1981. *A Catalog of Borehole Geophysics on the Hanford Site, 1958 to 1980*. PNL-3504. Pacific Northwest Laboratory, Richland, Washington.

CERCLA. *Comprehensive Environmental Response, Compensation, and Liability Act of 1980*, as amended, Public Law 96-510, 94 Stat. 2767, 42 USC 9601 et seq.

Chamness, M. A., R. E. Lewis, S. S. Teel, and A. W. Pearson. 1991a. *T Plant Geologic and Geophysics Data Package for the 200 Aggregate Area Management Study*. WHC-SD-EN-DP-022, Westinghouse Hanford Company, Richland Washington.

Chamness, M. A., S. S. Teel, D. L. McAlister, A. W. Pearson, K.R.O. Barton, R. W. Fruland, and R. E. Lewis. 1991b. *U-Plant Aggregate Area Management Study, Geologic Data Package*. WHC-SD-EN-DP-019, Westinghouse Hanford Company, Richland, Washington.

Chamness, M. A., S. S. Teel, D. L. McAlister, A. W. Pearson, K.R.O. Barton, R. W. Fruland, and R. E. Lewis. 1991c. *Z-Plant Aggregate Area Management Study, Geologic Data Package*. WHC-SD-EN-DP-020, Westinghouse Hanford Company, Richland, Washington.

Chamness, M. A., S. M. Goodwin, S. S. Teel, and R. E. Lewis. 1992a. *Semi-Works (C-Plant) Aggregate Area Management Study, Geologic Data Package*. WHC-SD-EN-DP-027, Westinghouse Hanford Company, Richland, Washington.

Chamness, M. A., R. E. Lewis, S. S. Teel, R. J. Brockman, D. C. Lanigan, and A. W. Pearson. 1992b. *PUREX Aggregate Area Management Study, Geologic Data Package*. WHC-SD-EN-DP-025, Westinghouse Hanford Company, Richland, Washington.

Chamness, M. A., D. L. McAlister, J. P. McDonald, A. W. Pearson, and R. E. Lewis. 1992c. *200 North Aggregate Area Management Study, Geologic Data Package*. WHC-SD-EN-DP-027, Westinghouse Hanford Company, Richland, Washington.

Chamness, M. A., and J. K. Merz. 1993. *Hanford Wells*. PNL-8800, Pacific Northwest Laboratory, Richland, Washington.

Delaney, C. D., K. A. Lindsey, and S. P. Reidel. 1991. *Geology and Hydrology of the Hanford Site: A Standardized Text for Use in Westinghouse Hanford Company Documents and Reports*. WHC-SD-ER-TI-003, Westinghouse Hanford Company, Richland, Washington.

DOE Order 5400.1, *General Environmental Protection Program*. U.S. Department of Energy, Washington, D.C.

DOE Order 5400.5, *Radiation Protection of the Public and Environment*. U.S. Department of Energy, Washington, D.C.

DOE. 1988. *Consultation Draft, Site Characterization Plan, Reference Repository Location, Hanford Site, Washington*. DOE/RW-0164, Vols. 1-9, Office of Civilian Radioactive Waste Management, U.S. Department of Energy, Washington, D.C.

DOE. 1996. *200 Areas Soil Remediation Strategy - Environmental Restoration Program*. DOE/RL-96-67, U.S. Department of Energy, Richland Operations Office, Richland, Washington.

DOE. 1997a. *Environmental Monitoring Plan, United States Department of Energy, Richland Operations Office*. DOE/RL-91-50, Rev. 2, U.S. Department of Energy, Richland Operations Office, Richland, Washington.

DOE. 1997b. *Waste Site Grouping for 200 Areas Soil Investigations*. DOE/RL-96-81, U.S. Department of Energy, Richland Operations Office, Richland, Washington.

Engelman, R. E., R. E. Lewis, D. C. Stromswold, and J. R. Hearst. 1995. *Calibration Models for Measuring Moisture in Unsaturated Formations by Neutron Logging*. PNL-10801, Pacific Northwest Laboratory, Richland, Washington.

EPA. 1986. *Test Methods for Evaluating Solid Wastes: Physical/Chemical Methods*, 3<sup>rd</sup> ed. SW-846, U.S. Environmental Protection Agency, Office of Solid Waste and Emergency Response, Washington, D.C.

EPA. 1994. *Guidance for the Data Quality Objectives Process*. EPA QA/G-4, Office of Research and Development, U.S. Environmental Protection Agency, Washington, D.C.

Fecht, K. R., G. V. Last, and K. R. Price. 1977. *Evaluation of Scintillation Probe Profiles from 200 Area Crib Monitoring Wells*. ARH-ST-156, Atlantic Richfield Hanford Company, Richland, Washington.

Fecht, K. R., S. P. Reidel, and A. M. Tallman. 1987. "Paleodrainage of the Columbia River System on the Columbia Plateau of Washington State - A Summary." In Schuster, J. G. (ed.), *Selected Papers on the Geology of Washington*. Bulletin 77, Division of Geology and Earth Resources, State of Washington Department of Natural Resources, Olympia, Washington, pp. 219-248.

Fecht, K. R., K. A. Lindsey, B. N. Bjornstad, D. G. Horton, G. V. Last, and S. P. Reidel. 1998. *An Atlas of Clastic Injection Dikes of the Pasco Basin and Vicinity*. BHI-01103, Bechtel Hanford, Inc., Richland, Washington.

Gilbert, R. O. 1987. *Statistical Methods for Environmental Pollution Monitoring*. Van Nostrand Reinhold Company Inc., New York.

Lewis, R. E., and A. W. Pearson. 1992. *A Catalog of Borehole Geophysics for the 100 Areas and Adjacent 600 Area, Hanford Site, 1962 to May 1992*. PNL-8230, Pacific Northwest Laboratory, Richland, Washington.

Lewis, R. E., and S. S. Teel. 1994. *A Survey of Existing and Emerging Technologies for External Detection of Liquid Leaks at the Hanford Site*. PNL-10176, Pacific Northwest Laboratory, Richland, Washington.

Lindsey, K. A. 1996. *The Miocene to Pliocene Ringold Formation and Associated Deposits of the Ancestral Columbia River System, South-Central Washington and North-Central Oregon*. Open-File Report 96-8, State of Washington Department of Natural Resources, Olympia, Washington.

McGhan, V. L., P. J. Mitchell, and R. S. Argo. 1985. *Hanford Wells*. PNL-5397, Pacific Northwest Laboratory, Richland, Washington.

Raymond, J. R., and V. L. McGhan. 1964. *Scintillation Probe Results - 200 Area Waste Disposal Site Monitoring Wells*. HW-84577, General Electric Company, Richland, Washington.

RCRA. *Resource Conservation and Recovery Act of 1976*, as amended, Public Law 94-580, 90 Stat. 2795, 42 USC 6901 et seq.

Reidel, S. P., K. A. Lindsey, and K. R. Fecht. 1992. *Field Trip Guide to the Hanford Site*. WHC-MR-0391, Westinghouse Hanford Company, Richland, Washington.

ROD. 1995. *Declaration of the Record of Decision, USDOE Hanford 100 Area, 100-BC-1, 100-DR-1, and 100-HR-1 Operable Units, Hanford Site, Benton County, Washington*. State of Washington Department of Ecology, U.S. Environmental Protection Agency, and U.S. Department of Energy, Richland Operations Office, Richland, Washington.

ROD. 1996. *Declaration of the Record of Decision for the 300-FF-1 and 300-FF-5 Operable Units*. State of Washington Department of Ecology, U.S. Environmental Protection Agency, and the U.S. Department of Energy, Richland Operations Office, Richland, Washington.

Sheen, E. M., W. L. Bunch, and M. R. Wood. 1964. *Neutron Soil Moisture Monitor*. HW-82009, General Electric Company, Richland, Washington.

State of Washington Department of Health. 1997. *Interim Regulatory Guidance, Hanford Guidance for Radiological Cleanup, Rev. 1*. Environmental Radiation Program, Division of Radiation Protection, Olympia, Washington.

Teel, S. S. 1992. *S-Plant Aggregate Area Management Study, Geologic Data Package*. WHC-SD-EN-DP-021, Westinghouse Hanford Company, Richland, Washington.

Teel, S. S., R. E. Lewis, M. A. Chamness, D. C. Lanigan, V. L. McGhan, and R. J. Brockman. 1992. *B-Plant Aggregate Area Management Study, Geologic Data Package*. WHC-SD-EN-DP-026, Westinghouse Hanford Company, Richland, Washington.

Tillson, D. D., and V. L. McGhan. 1969. *Changes in Scintillation Probe Findings - 1963 to 1968, 200 Area Waste Disposal Site Monitoring Wells*. BNWL-CC-2255, Pacific Northwest Laboratory, Richland, Washington.

U.S. Army Corps of Engineers. 1994. *Environmental Quality Requirements for the Preparation of Sampling and Analysis Plans*. Manual EM-200-1-3, Washington, D.C.

WAC 173-200, Washington Administrative Code. *Water Quality Standards for Ground Waters of the State of Washington*. Olympia, Washington.

WAC 173-303-645, Washington Administrative Code. *Dangerous Waste Regulations, Releases from Regulated Units*. Olympia, Washington.

WAC 173-340, Washington Administrative Code. *Model Toxics Control Act - Cleanup*. Olympia, Washington.

WAC 246-290, Washington Administrative Code. *Public Water Supplies*. Olympia, Washington.

Wilson, L. G., L. G. Everett, and S. J. Cullen (eds.). 1995. *Handbook of Vadose Zone Characterization & Monitoring*. Lewis Publishers, Boca Raton, Florida.

**THIS PAGE INTENTIONALLY  
LEFT BLANK**

## **Appendix A**

### **Quality Assurance Project Plan**

**THIS PAGE INTENTIONALLY  
LEFT BLANK**



## **Appendix A**

### **Quality Assurance Project Plan**

#### **A.1 Background Information**

Vadose zone monitoring activities are part of the overall objectives in support of the Hanford Groundwater Monitoring Project. Thus, the quality control/quality assurance (QC/QA) procedures for vadose zone monitoring shall be consistent with those of the Hanford Groundwater Monitoring Project. This Quality Assurance Project Plan (QAPjP) is intended to be used in all aspects of vadose zone monitoring. Implementation of the QA/QC requirements in this appendix will ensure that the vadose zone monitoring activities are carried out to achieve the specified data quality goals and that the quality of data gathered can be monitored and documented.

##### **A.1.1 QAPjP Applicability and Relationship to the Hanford Groundwater Monitoring Project QA Program**

This QAPjP applies specifically to various activities performed for vadose zone monitoring in support of the Hanford Groundwater Monitoring Project. This QAPjP is an element of the vadose zone monitoring plan prepared specifically for monitoring support to the Hanford Groundwater Monitoring Project and is consistent with other environmental work and the overall quality program requirements at the Hanford Site. Distribution and revision control of the monitoring plan, including this QAPjP, will comply with established Pacific Northwest National Laboratory (PNNL) procedures.

#### **A.2 Project Organization and Responsibilities**

##### **A.2.1 Technical Lead Responsibilities**

The PNNL Applied Geology and Geochemistry Group has primary responsibility for overseeing vadose zone monitoring aspects of the Hanford Groundwater Monitoring Project. The primary responsibility for the Hanford Groundwater Monitoring Project lies in PNNL's Field Hydrology and Chemistry Group.

##### **A.2.2 Analytical Data Acquisition Systems**

Data acquisition and analysis will be subcontracted to support organizations as described in Chapter 6.0 of the main text. All data collection, data reduction, and data analyses activities shall be performed in compliance with PNNL-reviewed and/or -approved QA plans and analytical procedures.

### **A.2.3 Health Physics**

Because the nature of many of the sites to be monitored render them contamination zones, radiation work permits and health physics support may be necessary.

### **A.2.4 Support Contractors**

Procurement of any contracted activities shall be in compliance with the PNNL Standards-Based Management System. Statements of work are to be reviewed and signed by the project quality engineer prior to submittal to contractors. All work shall be performed in compliance with PNNL-approved QA plans and/or procedures and shall be subject to assessment activities. Applicable quality requirements shall be invoked as part of the approved procurement documentation or work order.

## **A.3 Objectives for Measurements**

This project is a monitoring activity to obtain data that will be used to determine the subsurface configuration of contaminants. The overall data quality requirements to meet the intent of this proposal were determined as described in Chapter 4.0 of the main text. Detailed and specific data quality requirements for individual waste sites will be documented in the site-specific monitoring plans. The general requirements are discussed in the following sections.

### **A.3.1 General Precision and Accuracy Objectives**

As an outcome of the data quality objectives (DQO) process, the general requirement for precision and accuracy is intended to be such that changes in subsurface contaminant distribution or concentration can be documented. However, the individual site-specific monitoring plans take precedence in setting the specific specifications for precision and accuracy of the monitoring to be performed. The general guidance or objective may be accomplished differently for different monitoring methodologies. For example, geophysical logging may require relogging of specific repeat sections, whereas moisture or vapor-extraction techniques may require duplicate samples to meet the monitoring objective and/or to satisfy regulatory requirements or U.S. Department of Energy Orders.

### **A.3.2 Monitoring Measurements**

Representative analyses are necessary for accurate determination of subsurface contaminant distribution. Accurate interpretations of the subsurface data form the framework for subsequent decisions concerning remediation and for subsequent modeling of the subsurface. Monitoring measurements provide a means by which cleanup decisions and modeling can be accomplished.

#### **A.3.2.1 Monitoring Points**

Specific monitoring points are to meet site-specific DQOs and will be delineated in the site-specific monitoring plans.

#### **A.3.2.2 Constituents to be Measured**

The DQO process specified the constituents of concern/interest for vadose zone monitoring. Site-specific contaminants of concern are to be developed from the overall contaminants of concern and from site-specific inventories and delineated in the site-specific monitoring plans.

### **A.4 Measurement Procedures**

#### **A.4.1 Procedure Approvals and Control**

All procedures required for vadose zone monitoring activities shall be approved and shall comply with the requirements of the project. Where PNL-MA-568 (PNL 1994) procedures are referenced, equivalent procedures shall be used by subcontractors.

#### **A.4.2 Measurement Procedures**

This section describes procedures related to collecting monitoring data from boreholes and soil and pore fluid samples for the constituents of interest. Alternative measurement methods and procedures may be used but must be controlled and documented in accordance with the requirements in this QAPjP.

##### **A.4.2.1 $^{233,235,238}\text{U}$ , $^{137}\text{Cs}$ , $^{239,241}\text{Pu}$ , and $^{241}\text{Am}$**

Two borehole geophysical logging techniques can be used to measure the activity of the gamma-emitting isotopes of uranium, cesium, plutonium, and americium: gross gamma-ray logging and spectral gamma-ray logging. Gross gamma-ray logging gives a sum of the activities of all gamma-emitting radionuclides, whereas spectral gamma-ray logging gives activities for each individual radionuclide. These parameters are obtained by inserting gamma detectors into wells and boreholes. Borehole configuration specifics about casing type and seals must be known for quantitative corrections to gamma measurements. Also, accurate determinations of reference point, usually the top of casing, must be known. Most well casing elevations are surveyed to within  $\pm 0.01$  ft ( $\pm 0.3$  cm) and this accuracy is well within the requirements for vadose zone monitoring. Wells without accurate surveys must have a survey completed prior to monitoring. Procedures for borehole gamma-ray logging are vendor specific but must conform to the requirements of this QAPjP.

Fissionable radionuclides ( $^{233}\text{U}$ ,  $^{235}\text{U}$ , and  $^{239}\text{Pu}$ ) can be measured by prompt fission neutron logging in boreholes. These systems are commercially available, and measurement procedures are vendor specific. The system cannot distinguish among the fissionable radionuclides.

Gamma-emitting radionuclides can also be quantified by gamma spectrometry in a laboratory. Discrete samples of pore fluid are necessary. Laboratory-specific methods are used that are recognized as acceptable within the technical radiochemical industry (Gillespie 1998). Specific procedures are available through the PNNL technical contract administrator for the radiochemistry laboratory. The method involves direct counting using an intrinsic germanium or lithium-drifted germanium detector. Isotopes with gamma-ray energies from 60 to 2,000 KeV are detected.

In addition to gamma spectrometry, activities of alpha-emitting isotopes of uranium, plutonium, and americium can be measured in pore fluid samples by alpha spectrometry after isotopic separation by exchange resins. This method requires samples of pore fluid. Procedures are laboratory specific and recognized as acceptable within the technical radiochemical industry (Gillespie 1998).

#### **A.4.2.2 $^{99}\text{Tc}$ and $^{129}\text{I}$**

There are no readily available procedures for measurement of  $^{99}\text{Tc}$  and  $^{129}\text{I}$  in boreholes. However, laboratory procedures exist for the measurement of  $^{99}\text{Tc}$  and  $^{129}\text{I}$  activities in discrete samples of pore fluid. The procedures are laboratory specific and must conform to industry-recognized practice. Technetium and or iodine are chemically separated from the sample and  $^{99}\text{Tc}$  is measured by liquid-scintillation beta counting and  $^{129}\text{I}$  by a low-energy photon detector (Gillespie 1998).

#### **A.4.2.3 Chromium, Aluminum, Nitrate, Cyanide, and Carbon Tetrachloride**

Various laboratory procedures are available for analysis of these constituents of concern in samples of pore fluid. Laboratory procedures for the analysis of chromium and aluminum include flame atomic absorption according to Method 218.2 (EPA 1982), graphite furnace atomic absorption according to Method 7191 (EPA 1986), and inductively coupled plasma-mass spectrometry by Method 6020 (EPA 1986).

Field methods are available for measurement of chromium as described in Method 7196 (EPA 1986). However, there are no readily available procedures for measurement of chromium in the vadose zone in boreholes.

Aluminum can be measured in boreholes by pulsed-neutron logging. Procedural methods are vendor specific. The use of pulsed-neutron logging for measurement of soluble aluminum is not practical at the Hanford Site because the technique will measure all aluminum around the borehole, including that in aluminosilicate minerals.

Cyanide in pore fluid can be measured by Methods 1910 and 1912 (EPA 1986). There is no readily available procedure for measurement of cyanide in the vadose zone in boreholes.

Carbon tetrachloride is measured in the laboratory by gas chromatography per Method 8260 (EPA 1986). There are also several available methods for measurement of carbon tetrachloride in the field. The method currently used by the soil-vapor extraction project is infrared photoacoustic spectrometry following the manufacturer's recommended procedure. Although not proven at the Hanford Site, carbon

tetrachloride can also be measured by pulsed-neutron logging using vendor-specific procedures. The actual measurement is Cl and C, so that other compounds with these elements will be included as part of the measured result.

The laboratory procedures for the analysis of nitrate in pore fluid are ion chromatography (Methods 300.0 or 9056 [EPA 1984, 1986, respectively]). Field methods are available for measurement of nitrate in water samples but there are no readily available procedures for measurement of nitrate in the vadose zone in boreholes.

#### **A.4.2.4 Water Content, Matric Potential, and Water Flux**

There are numerous methods for the measurement of these parameters (see Table 6.2 in the main text). Lewis and Teel (1994) evaluated the following methods as having potential at the Hanford Site. Borehole methods include neutron-neutron logging, pulsed-neutron spectroscopy logging, and electrical induction logging. Cross-borehole methods include electrical resistivity tomography and shear-wave seismic tomography. In situ, soil-moisture instrumentation methods include time-domain reflectometry and resistivity blocks. Lysimeters and membrane/filter samplers can collect pore fluid samples for either measurement of the soil-moisture content or dissolved constituents. Analytical laboratory measurement of moisture is usually gravimetric.

Procedures approved by the U.S. Environmental Protection Agency do not exist for many of the techniques listed in Table 6.2 of the main text. Vendor-specific procedures or manufacturer's recommended procedures are available for most commercially available methods. Several standards exist for neutron-neutron logging (ASTM D5220-92, Standard Test Method for Water Content of Soil and Rock In-Place by the Neutron Depth Probe Method; ASTM D3017-96e1, Standard Test Method for Water Content of Soil and Rock In-Place by Nuclear Methods [Shallow Depth]; and ASTM D6031-96, Standard Test Method for Logging In-Situ Moisture Content and Density of Soil and Rock by the Nuclear Method in Horizontal, Slanted and Vertical Access Tubes); for direct sampling and ex situ analysis (ASTM D4696, Standard Guide for Pore-Liquid Sampling from the Vadose Zone; ASTM D2216, Percent Moisture Analysis); and for field measurement of water content or hydrologic properties (ASTM D5126-90, Standard Guide for Comparison of Field Methods for Determining Hydraulic Conductivity in the Vadose Zone; ASTM D3152-72[1994]e1, Standard Test Method for Capillary Moisture Relationships for Fine-Textured Soils by Pressure Membrane Apparatus; ASTM D2325-68[1981]e1, Standard Test Method for Capillary Moisture Relationships for Coarse- and Medium-Textured Soils by Porous-Plate Apparatus; ASTM D5298-94, Standard Test Method for Measurement of Soil Potential [Suction] Using Filter Paper; and ASTM D5093-90, Standard Test Method for Field Measurement of Infiltration Rate Using a Double-Ring Infiltrometer with a Sealed Inner Ring).

#### **A.4.2.5 Other Procedures**

If it is determined that other procedures are required that are not already identified in this QAPjP, they will be identified in the appropriate site-specific monitoring plan. Documentation requirements shall be addressed within individual procedures.

### **A.4.3 Procedure Changes**

Should deviations from established procedures be required to accommodate unforeseen field situations, they may be authorized by the project lead for the site-specific monitoring concerned in accordance with the requirements in the applicable statements of work, site-specific requirements, and applicable vendor-specific procedures. Deviations from established procedures must be documented in the project files.

### **A.5 Sample Handling**

All data obtained during the course of vadose zone monitoring activities shall be controlled as required by this QAPjP and the established PNNL groundwater monitoring project QA project plan. Chain-of-custody procedures shall be used that maintain sample integrity and identification throughout the analytical process. Chain-of-custody forms shall be initiated for returned residual samples. Results of analyses shall be traceable to original samples through unique code or identifier specified in the site-specific monitoring plan. In general, chain of custody is not required for borehole measurement techniques. However, header sheets containing location, dates, techniques, and other information are required to be a permanent attachment to each geophysical log data set. All results of data analyses shall be controlled as permanent project quality records as required by standard PNNL procedures.

### **A.6 Calibration Procedures**

All measuring and test equipment shall be calibrated in compliance with the requirements of applicable procedures. Equipment that requires user calibration or field adjustment shall be calibrated as required by standard procedures.

Borehole logging equipment will be calibrated according to industry standard procedures maintained by the vendors conducting the logging. Two calibrations are applicable to borehole logging: a depth calibration of the cable and cable hoist system and a calibration of the detector and associated electronics.

All calibration of laboratory measuring and test equipment shall meet the minimum requirements of the PNNL groundwater monitoring project QA project plan. Such requirements shall be invoked through PNNL procurement control procedures. All subcontractor QA plans shall address equipment to be calibrated and the calibration schedules.

### **A.7 Analytical Procedures**

Analytical methods are identified and discussed above and in appropriate site-specific monitoring plans. All analytical procedures used to support this proposal shall comply with EPA (1986) where possible. All analytical procedures approved for use in vadose zone monitoring shall require the use of

standard reporting techniques and units wherever possible to facilitate the comparability of data sets in terms of precision and accuracy. All approved procedures shall be retained in the project QA records and shall be available for review on request.

## **A.8 Data Reduction, Validation, and Reporting**

Data from monitoring activities will be used primarily to determine the presence and amounts of contaminants of interest in specified locations and intervals. The support organization responsible for acquiring the monitoring data shall be responsible for the examination and verification of results to the extent appropriate. The requirements discussed in this section shall be invoked, as appropriate, in procurement documentation prepared in compliance with standard PNNL procedures. Results from all monitoring measurements shall be summarized in required reports and supported by QC checks, equipment calibration data, spectra, or other verification data as appropriate.

Project records shall be managed according to established PNNL records management procedures. All reports and supporting data may be subjected to a detailed technical review by a qualified reviewer. All reports, technical reviews, and supporting data shall be retained as permanent project QA records in compliance with referenced procedures.

## **A.9 Internal QC**

The quality of vadose zone monitoring data shall be subject to in-process QC checks in the field, during data reduction, or in the laboratory, as appropriate. Minimum requirements are defined as follows.

Specific field checks shall be appropriate to the specific monitoring method and be documented in site-specific monitoring plans. Unless otherwise specified in a site-specific monitoring plan, minimum field QC checks for borehole logging activities shall include the following:

- Pre- and post-monitoring detector verification will be done using a known and documented source. Acceptance criteria are to be documented in applicable procedures.
- A minimum of 3 m (10 ft) in each borehole is to be relogged as a QC sample. The portion of the borehole to be relogged can be at the discretion of the log operator.

Internal QC checks performed by the analytical laboratories shall be in compliance with approved analytical procedure requirements.

## **A.10 Performance and System Assessments**

Acceptable performance for vadose zone monitoring is defined as compliance with the requirements of this QAPjP, its implementing procedures, the associated site-specific monitoring plans, and other applicable PNNL QA program plans. All activities addressed by this QAPjP are subject to assessments of project performance and systems adequacy. Assessments shall be conducted in accordance with appropriate PNNL procedures and shall be scheduled at the discretion of the cognizant quality engineer or technical lead.

## **A.11 Preventive Maintenance**

All measurement and testing equipment used in the field and in laboratories that directly affects the quality of the monitoring data shall be subject to preventive maintenance measures. These measures are designed to ensure the availability of instrumentation and the reliability of operation to prevent delays or loss of data. Subcontractors shall be responsible for performing or managing the maintenance of their equipment; maintenance requirements, spare parts lists, and instructions shall be included in individual methods or in subcontractor QA plans. All QA plans shall be subject to PNNL review and approval.

## **A.12 Corrective Action**

Corrective action requests required as a result of assessment reports shall be documented and dispositioned as required by standard PNNL corrective action procedures. Primary responsibilities for corrective action resolution are assigned to the project technical lead and the quality engineer.

Other measurement systems, procedures, or plan corrections that may be required as a result of routine review processes shall be resolved as required by governing procedures or shall be referred to the technical lead for resolution. Copies of all assessment documentation shall be routed to the project QA records on completion or closure.

## **A.13 QA Reports**

Project performance shall be evaluated by the assessment process. Assessment documentation shall be routed to the project records on completion or closure of the activity. A report summarizing assessment activity, as well as any associated corrective actions, shall be prepared by the QA coordinator at the completion of the project.



## A.14 References

EPA. 1982. *Methods for Chemical Analysis of Water and Waste*. EPA-600/4-82-055, U.S. Environmental Protection Agency, Washington, D.C.

EPA. 1984. *Test Method: The Determination of Inorganic Anions in Waster by Ion Chromatography - Method 300.0*. EPA-600/4-84-17, U.S. Environmental Protection Agency, Washington, D.C.

EPA. 1986. *Test Methods for Evaluating Solid Waste - Physical/Chemical Methods*. SW-846 (3rd Edition), Office of Solid Waste and Energy Response, U.S. Environmental Protection Agency, Washington, D.C.

Gillespie, B. M. 1998. "Appendix C, Analytical Methods." In Hartman, M. J. and P. E. Dresel, *Hanford Site Groundwater Monitoring for Fiscal Year 1997*. PNNL-11973, Pacific Northwest National Laboratory, Richland, Washington.

Lewis, R. E., and S. S Teel. 1994. *A Survey of Existing and Emerging Technologies for External Detection of Liquid Leaks at the Hanford Site*. PNL-10176, Pacific Northwest Laboratory, Richland, Washington.

PNL. 1994. *Procedures for Groundwater Investigations*. PNL-MA-567, Pacific Northwest Laboratory, Richland, Washington.

**THIS PAGE INTENTIONALLY  
LEFT BLANK**

## Appendix B

## Site Prioritization

**THIS PAGE INTENTIONALLY  
LEFT BLANK**

# Appendix B

## Site Prioritization

### B.1 Introduction

This appendix describes the process used to prioritize liquid waste disposal sites.

Eleven criteria resulted from the data quality objectives (DQO) process (see Chapter 4.0 in the main text). Each criterion was applied to each waste site to help determine the potential need for vadose zone monitoring.

1. Is there a current threat imposed by site conditions on the environment?
2. Is there a regulatory reason to monitor?
3. Are there mobile contaminants associated with the site?
4. Are there long-lived contaminants associated with the site?
5. Have mobile constituents been "flushed" from the vadose zone?
6. Is there a potential for future impact to groundwater?
7. Are there vadose zone plumes associated with the site?
8. Is there a current impact to groundwater at the site?
9. Is the site in an area that is currently receiving liquid effluent?
10. Are there driving forces external to the site?
11. Are characterization and/or baseline data available?

The waste sites evaluated for this proposal were all the waste sites in the 200 Areas as reported in *Waste Site Grouping for 200 Areas Soil Investigations* (Table A.1 in DOE 1997). The *Waste Site Grouping for 200 Areas Soil Investigations* placed each of 662 waste sites into 1 of 23 waste site groups that were previously developed by the *200 Areas Soil Remediation Strategy - Environmental Restoration Program* (DOE 1996). The placement primarily was based on the chemical processes generating the waste streams disposed to the facilities. The waste site groups were then prioritized (as groups) on the basis of past, current, and potential future impacts to groundwater, contaminant types and contaminant chemistry, geographic location, and other parameters (DOE 1997). Many of the decision rules developed during the DQO process for this proposal are similar to the criteria used by the *Waste Site Grouping for 200 Areas Soil Investigations* to prioritize waste site groups.

### B.2 Prioritization Process

The first criterion is "Is there a current threat imposed by site conditions on the environment?" No sites from Table A.1 in the *Waste Site Grouping for 200 Areas Soil Investigations* received a positive

response to this question. However, one site in the 100 K Area (the 100 KE Basin) received a positive response to this question because it contributes potentially significant inventories of fission products and transuranics to the soil column (Johnson et al. 1995) and because of its proximity to the Columbia River. Thus, the 100 KE Basin is included on the priority list.

The second criterion is "Is there a regulatory reason to monitor?" Although there are no U.S. Environmental Protection Agency or State of Washington Department of Ecology regulations requiring vadose zone monitoring at any of the facilities included in the *Waste Site Grouping for 200 Areas Soil Investigations*, monitoring is being considered as an alternative or an extension of groundwater monitoring at the Liquid Effluent Retention Facility (LERF) because changes in the groundwater system beneath that facility will soon make the LERF noncompliant with established groundwater protection standards (40 CFR 265, WAC 173-303-645). For this reason, the LERF is included on the priority list. All the sites in the *Waste Site Grouping for 200 Areas Soil Investigations* are covered by DOE Order 5400.1.

Criteria 3 and 4 determine whether there are constituents of concern associated with the sites. The constituents of concern are the mobile contaminants ( $^{99}\text{Tc}$ ,  $^{129}\text{I}$ , nitrate, uranium, chromium, carbon tetrachloride, cyanide, and soluble aluminum), the immobile and/or long-lived contaminants (plutonium, americium and cesium), and moisture (driving force) (see Decision Inputs, Section 4.6 in the main text). The *Waste Site Grouping for 200 Areas Soil Investigations* included inventories for all these constituents, except  $^{99}\text{Tc}$ ,  $^{129}\text{I}$ , aluminum, and moisture. Data for  $^{99}\text{Tc}$  and  $^{129}\text{I}$  were obtained from the cumulative decayed inventory reports maintained by Waste Management Federal Services, Inc. and were included with the other data. It should be noted that in searching for this information, differences were found in reported quantities for  $^{99}\text{Tc}$  and  $^{129}\text{I}$ , depending on the source examined. No data for aluminum were found in an electronic format to include in this evaluation. Some inventory data on aluminum in effluent do exist for some sites and will be compiled for inclusion in subsequent evaluations for potential vadose zone monitoring. Moisture is considered later, when driving forces are evaluated.

Application of criteria 3 and 4 yielded over 200 sites that have associated constituents of concern. The vast majority of the sites without inventoried constituents of concern were unplanned releases, landfills and dumps, and septic tanks and drain fields.

The next step in the evaluation considered criteria 5, 6, and 7. It was assumed that sites where mobile contaminants have been flushed from the vadose zone have already impacted groundwater (criterion 8).

The number of pore volumes disposed to each facility was determined by dividing the effluent volumes by the pore volumes. The volume data used were reported in DOE (1997). Less than or equal to 10 pore volumes was the delimiting volume for this evaluation, based on the fact that anything over 1 pore volume would have introduced mobile constituents to the groundwater. In such cases, vadose monitoring as an early detection system for protection of groundwater is "after the fact." Ten pore volumes were chosen as the conservative measure.

Forty-one sites did not have the volume information to calculate the number of pore volumes, 61 sites had more than 10 pore volumes disposed, and 114 had less than or equal to 10 pore volumes disposed to

them. Data for the 41 sites with no volume information will be sought and, if available, included in subsequent evaluations. About half of the 41 sites are radioactive landfills and dumps.

Fifty-six of the 61 sites with greater than 10 pore volumes have associated long-lived, relatively immobile constituents of concern. Because the long-lived constituents of concern can remain in the soil column even after 10 pore volumes, those sites are retained as intermediate-priority sites.

Criteria 9 and 10 were considered next. Basically, three potential sources for a driving force were considered: 1) is the site actively receiving effluent, 2) is the site influenced by a known source of water recharge from man-made systems, and 3) natural recharge.

Except for LERF and the 100-KE Basin, none of the sites that received less than or equal to 10 pore volumes is an active site. Whether a site is influenced by a known source of water recharge from a man-made system is more difficult to answer. The *Waste Site Grouping for 200 Areas Soil Investigations* considered this aspect and concluded that none of the sites was within 30 m of a known source of water recharge from man-made systems (DOE 1997, p. 5-6). An effort is under way to identify facilities that may be impacted by leaking or broken water lines, storm runoff systems, or other man-made facilities. Results of that effort will be incorporated in subsequent evaluations once they are available; but until that time, the conclusion of the waste site grouping (DOE 1997) is used.

The last aspect, natural recharge, was evaluated by plotting each of the 114 sites with constituents of concern and less than or equal to 10 pore volumes on an updated version of the Hanford Site recharge map produced by Fayer et al. (1996). For sites within disturbed areas, Fayer et al. (1996) estimated recharge assuming there were no plants and the soil type was what it was prior to Hanford Site operations. For sites outside disturbed areas, they used the pre-Hanford soil type with the vegetative cover defined by the vegetation map of Downs et al. (1993). It is recognized that these assumptions may not represent actual cover on the waste sites. The application of natural recharge to the site prioritization can be updated as newer information becomes available. Also, any enhancement of infiltration resulting from local topographic features will be accounted for during evaluation of specific sites.

Most waste sites fell into the 50- to 100-mm/year areas on the recharge map because they lie in disturbed areas and Fayer et al. (1996) treated these areas as bare soil. All other facilities fell into the 0.5- to 5-, 5- to 10-, or the 10- to 20-mm/yr recharge zones. Sites in higher recharge zones receive higher priority for vadose zone monitoring than do sites in lower recharge zones.

Criterion 11 is "Are characterization and/or baseline data available?" for comparison with new monitoring data. Several sources of past monitoring and characterization information were checked to see whether data were available and published. Most sources of historical monitoring data were gross gamma-ray and spectral gamma-ray log data. A cutoff date of 1977 was made for consideration of such data because data collected before that time are considered to have too many associated unknowns for comparison with current data. The major sources of baseline data are Fecht et al. (1977), Additon et al. (1978a, 1979b), Brodeur et al. (1993), and part of a very recently completed Pacific Northwest National Laboratory database of spectral gamma-ray logs that have been collected since about 1991.

Numerous published characterization studies that report laboratory and field testing results can be found. Many of these reports probably contain data suitable as baseline for vadose zone monitoring. A thorough search for these reports was not made, however, because of the monumental effort that would be involved. Site-specific monitoring plans must consider this source of information.

Sixty sites with less than or equal to 10 pore volumes and associated contaminants of concern also have identified baseline data (Table B.1). The 54 sites without baseline data (Table B.2) are recommended as sites for which some sort of characterization information is needed if future monitoring is to be done at those sites. These sites are retained as intermediate priority sites. In some instances, initial characterization data may also serve as initial monitoring data.

### **B.3 Prioritization Results**

The results of this evaluation are shown in Tables B.1, B.2, and B.3. Table B.1 shows the 62 high-priority sites. These are the sites with associated constituents of concern, less than or equal to 10 pore volumes, and have associated baseline information for monitoring.

Table B.2 shows the intermediate-priority sites that have associated constituents of concern, less than 10 pore volumes but no associated baseline information for monitoring. Table B.3 shows the intermediate-priority sites that have long-lived, relatively immobile constituents of concern but received greater than 10 pore volumes of effluent.

All sites have been further prioritized within each of Tables B.1, B.2, and B.3. First, the relative ranking of waste site groups has been retained from the *Waste Site Grouping for 200 Areas Soil Investigations* (DOE 1997). Then, within each waste site group, sites are ranked first by waste site type, second by amount of natural recharge, and third by the date that the site was last monitored.

Specific retention facilities were designed to use the moisture-retention capability of the soils to retain contaminants. Ideally, liquid disposed to specific retention facilities was to be limited to 6% to 10% of the soil volume between the facility and the groundwater so that the groundwater would not be impacted (Waite 1991). Specific retention facilities were used at the Hanford Site between 1951 and 1958 for tank waste. Because of their history and intended use, specific retention facilities are considered higher priority than the other facility types on the tables (except for LERF and KE Basin). (There is discrepancy among sources as to the name and type of many of the liquid waste disposal facilities at Hanford.) By placing specific retention facilities higher on the list than other sites, most sites with fewer than 1 pore volume are at the top of the lists.

### **B.4 Monitoring Recommendation**

Two recommendations are made concerning sites for potential vadose zone monitoring. First, the priority sites listed in Table B.1 should be considered first for future monitoring. Particular emphasis is



**Table B.1. Liquid Disposal Sites with Constituents of Concern, Less Than 11 Pore Volumes,  
and Baseline Information**

Site	Facility Type	Mobile Constituents	Immobile or Long-Lived Constituents	Number of Pore Volumes	Natural Recharge (mm/yr)	Baseline Information
<b>Potential Environmental Impact</b>						
KE Basin	Fuel storage basin				10 - 20	
LERF	RCRA TSD				0.5 - 5	
<b>Uranium-Rich Process Condensate/Process Waste Group</b>						
216-A-1	Specific retention crib	U Tc NO3	Pu Cs	0.0	50 - 100	1977, 1978
216-A-18	Specific retention crib	U Tc NO3	Pu Cs	0.0	50 - 100	1978
<b>Plutonium/Organic-Rich Process Condensate/Process Waste Group</b>						
216-Z-1A	Tile field	Tc CCl4 NO3	Pu Am Cs	0.1	50 - 100	1977, 1978, 1993
216-Z-9	Enclosed trench	U Tc CCl4 NO3	Pu Am Cs	1.6	50 - 100	1977, 1978, 1993
216-Z-18	Crib	CCl4 NO3	Pu	0.3	50 - 100	1977, 1978, 1993
<b>Organic-Rich Process Condensate/Process Waste Group</b>						
216-S-13	Specific retention crib	U Tc NO3 Cr	Pu Cs	1.9	50 - 100	1977, 1978, 1993
216-A-2	Specific retention crib	U Tc	Pu Cs	0.2	0.5 - 5	1977, 1978
216-A-31	Specific retention crib	U Tc	Pu Cs	0.0	0.5 - 5	1977, 1978
216-A-7	Crib	U Tc	Pu Cs	1.5	50 - 100	1978
<b>Fission Product-Rich Process Condensate/Process Waste Group</b>						
216-B-50	Crib	U Tc NO3	Pu Cs	5.5	10 - 20	1977
216-S-9	Crib	U Tc NO3	Pu Cs	3.3	50 - 100	1977, 1978
<b>General Process Condensate and Process Waste Group</b>						
216-C-5	Specific retention crib	U Tc	Pu Cs	0.1	50 - 100	1977
216-S-22	Crib	U Tc NO3	Pu Cs	0.2	50 - 100	1977, 1978
216-S-23	Crib	U Tc NO3	Pu Cs	5.7	50 - 100	1977, 1978
<b>Tank Waste Group</b>						
216-T-5	Specific retention trench	U Tc NO3	Pu Cs	2.7	50 - 100	1977, 1978
216-B-41	Specific retention trench	U Tc NO3	Pu Cs	0.3	10 - 20	1977, 1978
216-B-38	Specific retention crib	U Tc NO3	Pu Cs	0.3	10 - 20	1993
216-B-36	Specific retention trench	U Tc NO3	Pu Cs	0.4	10 - 20	1977, 1978, 1993
216-T-14	Specific retention trench	U Tc NO3	Pu Cs	0.2	0.5 - 5	1977, 1978
216-T-15	Specific retention trench	U Tc NO3	Pu Cs	0.2	0.5 - 5	1977, 1978
216-T-21	Trench	U Tc NO3	Pu Cs	0.1	50 - 100	1978
216-T-22	Trench	U Tc NO3	Pu Cs	0.4	50 - 100	1978
216-T-23	Trench	U Tc NO3	Pu Cs	0.4	50 - 100	1993
216-B-9	Crib and tile field	U Tc NO3	Pu Cs	1.4	50 - 100	1977, 1978, 1993
216-B-8	Crib and tile field	U Tc NO3	Pu Cs	0.5	10 - 20	1977, 1978
216-T-17	Trench	U Tc NO3	Pu Cs	0.2	0.5 - 5	1993
<b>Scavenged Waste Group</b>						
216-B-20	Specific retention trench	U Tc CN NO3	Pu Cs	0.3	50 - 100	1977, 1978
216-B-21	Specific retention trench	U Tc CN NO3	Pu Cs	0.3	50 - 100	1977, 1978
216-B-22	Specific retention trench	U Tc CN NO3	Pu Cs	0.3	50 - 100	1977, 1978
216-B-24	Specific retention trench	U Tc CN NO3	Pu Cs	0.3	50 - 100	1977, 1978
216-B-26	Specific retention trench	U Tc CN NO3	Pu Cs	0.4	50 - 100	1977, 1978
216-B-28	Specific retention trench	U Tc CN NO3	Pu Cs	0.4	50 - 100	1977, 1978
216-B-29	Specific retention trench	U Tc CN NO3	Pu Cs	0.4	50 - 100	1977, 1978

Table B.1. (contd)

Site	Facility Type	Mobile Constituents	Immobile or Long-Lived Constituents	Number of Pore Volumes	Natural Recharge (mm/yr)	Baseline Information
216-B-31	Specific retention trench	U Tc CN NO3		0.4	50 - 100	1977, 1978
216-B-34	Specific retention trench	U Tc CN NO3	Pu Cs	0.4	50 - 100	1977, 1978
216-T-18	Specific retention crib	U Tc NO3	Pu Cs	1.4	50 - 100	1977, 1978, 1993
216-B-42	Specific retention trench	U Tc CN NO3	Pu Cs	0.3	10 - 20	1978
216-B-15	Crib	U Tc CN NO3	Pu Cs	0.4	50 - 100	1977, 1978
216-B-17	Crib	U Tc CN NO3	Pu Cs	0.2	50 - 100	1977, 1978
216-B-19	Crib	U Tc CN NO3	Pu Cs	0.4	50 - 100	1977, 1978
216-B-14	Crib	U Tc CN NO3	Pu Cs	0.5	50 - 100	1977, 1978, 1993
216-B-16	Crib	U Tc CN NO3	Pu Cs	0.3	50 - 100	1977, 1978, 1993
216-B-18	Crib	U Tc CN NO3	Pu Cs	0.5	50 - 100	1977, 1978, 1993
216-B-43	Crib	U Tc CN NO3	Pu Cs	0.2	10 - 20	1977, 1978
216-B-44	Crib	U Tc CN NO3	Pu Cs	0.6	10 - 20	1977, 1978
216-B-45	Crib	U Tc CN NO3	Pu Cs	0.5	10 - 20	1977, 1978
216-B-46	Crib	U Tc CN NO3	Pu Cs	0.7	10 - 20	1977, 1978
216-B-47	Crib	U Tc CN NO3	Pu Cs	0.4	10 - 20	1977, 1978
216-B-48	Crib	U Tc CN NO3	Pu Cs	0.4	10 - 20	1977, 1978
216-B-51	French drain	NO3		0.0	10 - 20	1977, 1993
<b>Steam Condensate Group</b>						
216-T-36	Crib	U Tc	Pu Cs	0.1	50 - 100	1977, 1978
<b>Gable Mountain/B Pond and Ditch Cooling Water Group</b>						
216-A-40	Specific retention trench	NO3		0.1	50 - 100	1978
<b>200 Areas Chemical Laboratory Waste Group</b>						
216-B-10B	Crib	Tc	Cs	0.1	50 - 100	1977, 1978
216-T-8	Crib	U Tc Cr	Pu Cs	0.4	50 - 100	1978
216-Z-7	Crib	U Tc NO3	Pu Cs	2.6	50 - 100	1977, 1978, 1993
<b>300 Areas Chemical Laboratory Waste Group</b>						
216-T-34	Crib	U Tc NO3	Pu Cs	2.8	0.5 - 5	1977, 1978
216-T-35	Crib	U Tc NO3	Pu Cs	0.4	0.5 - 5	1977, 1978, 1993
<b>Miscellaneous Waste Group</b>						
216-A-4	Specific retention crib	U Tc NO3 Cr	Pu Cs	6.6	0.5 - 5	1977, 1978
216-T-33	Crib	U Tc	Pu Cs	2.8	0.5 - 5	1977, 1978
216-A-27	Crib	U Tc Cr	Pu Cs	4.6	0.5 - 5	1977, 1978, 1993
<b>Sources of Baseline Information</b>						
Fecht et al. (1977).						
Additon et al. (1978a, 1978b).						
Brodeur et al. (1993).						
All other information from Pacific Northwest National Laboratory database						
RCRA = Resource Conservation and Recovery Act.						
TSD = Treatment, storage, and disposal (unit).						

**Table B.2. Liquid Disposal Sites with Constituents of Concern, Less Than 11 Pore Volumes, and No Baseline Information**

Site	Facility Type	Mobile Constituents	Immobile or Long-Lived Constituents	Number of Pore Volumes	Natural Recharge (mm/yr)	Baseline
<b>Uranium-Rich Process Condensate/Process Waste Group</b>						
216-A-19	Specific retention trench	U Tc NO3	Pu Cs	0.9	50 - 100	
216-A-20	Specific retention trench	U Tc NO3	Pu Cs	0.8	50 - 100	
216-B-60	Specific retention crib	U Tc		0.0	50 - 100	
216-A-28	Crib	U Tc NO3		0.2		
216-S-8	Trench	U Tc NO3	Pu Cs	1.0	50 - 100	
216-U-5	Trench	U Tc NO3		1.4	50 - 100	
216-U-6	Trench	U Tc NO3		1.4	50 - 100	
216-A-3	Crib	U Tc	Pu Cs	3.2	50 - 100	
<b>Plutonium-Rich Process Condensate/Process Waste Group</b>						
216-Z-4	Crib	U Tc	Pu Cs	0.1	50 - 100	
216-Z-6	Crib	U Tc NO3	Pu Cs	0.2	50 - 100	
216-Z-8	French drain		Pu Am	0.9	50 - 100	
<b>Organic-Rich Process Condensate/Process Waste Group</b>						
216-U-15	Trench	U Tc	Pu Cs	0.1	50 - 100	
216-C-4	Crib	U Tc	Pu Cs	0.4	50 - 100	
<b>Fission Product-Rich Process Condensate/Process Waste Group</b>						
216-C-6	Crib	U Tc	Pu Cs	1.1	50 - 100	
<b>General Process Condensate and Process Waste Group</b>						
216-C-7	Crib	U Tc	Pu Cs	0.1	50 - 100	
216-T-20	Trench	U Tc NO3	Cs	0.3	50 - 100	
216-U-17	Crib	U	Am	1.0	50 - 100	
216-A-45	Crib	U Tc I	Am Cs	1.8	50 - 100	
216-C-10	Crib	U Tc	Pu Cs	2.3	50 - 100	
216-C-3	Crib	U Tc I	Pu Cs	4.1	50 - 100	
216-S-4	French drain	NO3		6.7		
<b>Tank Waste Group</b>						
216-B-35	Specific retention trench	U Tc NO3	Pu Cs	0.2	10 - 20	
216-B-39	Specific retention trench	U Tc NO3	Pu Cs	0.3	10 - 20	
216-B-40	Specific retention trench	U Tc NO3	Pu Cs	0.3	10 - 20	
216-B-37	Specific retention trench	U Tc NO3	Pu Cs	0.8	10 - 20	
216-T-16	Specific retention trench	U Tc NO3	Pu Cs	0.2	0.5 - 5	
216-T-24	Specific retention trench	U Tc NO3	Pu Cs	0.4	50 - 100	
216-T-25	Specific retention trench	U Tc NO3	Pu Cs	1.1	50 - 100	
<b>Scavenged Waste Group</b>						
216-B-25	Specific retention	U Tc CN NO3	Pu Cs	0.3	50 - 100	
216-B-27	Specific retention	U Tc CN NO3	Pu Cs	0.3	50 - 100	
216-B-23	Specific retention	U Tc CN NO3	Pu Cs	0.3	50 - 100	
216-B-30	Specific retention	U Tc CN NO3	Pu Cs	0.4	50 - 100	
216-B-32	Specific retention	U Tc CN NO3	Pu Cs	0.4	50 - 100	
216-B-33	Specific retention	U Tc CN NO3	Pu Cs	0.4	50 - 100	
216-B-52	Specific retention crib	U Tc CN NO3	Pu Cs	0.5		
216-B-49	Crib	U Tc CN NO3	Pu Cs	0.7	10 - 20	

Table B.2. (contd)

Site	Facility Type	Mobile Constituents	Immobile or Long-Lived Constituents	Number of Pore Volumes	Natural Recharge (mm/yr)	Baseline
<b>Gable Mountain/B Pond and Ditch Cooling Water Group</b>						
216-B-2-2	Ditch		Pu Cs	0.7	50 - 100	
216-C-9	Pond		Pu Cs	5.3	50 - 100	
<b>200 North Pond Cooling Water Group</b>						
216-N-5	Crib	Tc	Cs	4.4	0.5 - 5	
216-N-7	Crib	Tc	Cs	4.9	0.5 - 5	
216-N-3	Crib	Tc	Cs	5.1	0.5 - 5	
216-N-4	Pond	U	Pu Cs	7.3	0.5 - 5	
216-N-6	Pond	U	Pu Cs	9.7	0.5 - 5	
<b>S Ponds/Ditches Cooling Water Group</b>						
216-S-17	Pond	U NO3	Pu Cs	4.2	50 - 100(?)	
<b>T Ponds/Ditches Cooling Water Group</b>						
216-T-1	Ditch	U	Pu Cs	4.7	0.5 - 5	
<b>200 Areas Chemical Laboratory Waste Group</b>						
216-S-19	Pond	U	Pu Cs	5.2	10 - 20(?)	
216-U-4	Dry well	NO3		0.0	50 - 100	
216-U-4B	French drain	Tc NO3	Pu Cs	3.0	50 - 100	
<b>300 Areas Chemical Laboratory Waste Group</b>						
216-B-53B	Specific retention trench	U Tc NO3	Pu Cs	0.0	50 - 100	
216-B-58	Specific retention trench	U Tc NO3	Pu Cs	0.1	50 - 100	
216-B-54	Specific retention trench	U Tc NO3	Pu Cs	0.2	50 - 100	
216-B-53A	Specific retention trench	U Tc NO3	Pu Cs	0.3	50 - 100	
<b>Miscellaneous Waste Group</b>						
216-U-13	Trench	U Tc	Pu Cs	0.0	50 - 100	
216-S-12	Trench	U Tc	Pu Cs	0.0	50 - 100	

placed on LERF, KE Basins, and specific retention facilities. Second, because of their use and history, specific retention facilities included on Table B.2 should receive second priority despite there being no baseline data.

## B.5 References

40 CFR 265, Code of Federal Regulations, Title 40, Part 265. *Interim Status Standards for Owners and Operators of Hazardous Waste Treatment, Storage, and Disposal Facilities.*

Additon, M, K., K. R. Fecht, T. L. Jones, and G. V. Last. 1978a. *Scintillation Probe Profiles, 200 East Area Crib Monitoring Wells.* RHO-LD-28, Rockwell Hanford Operations, Richland, Washington.

Additon, M, K., K. R. Fecht, T. L. Jones, and G. V. Last. 1978b. *Scintillation Probe Profiles, 200 West Area Crib Monitoring Wells.* RHO-LD-29, Rockwell Hanford Operations, Richland, Washington.

**Table B.3. Liquid Disposal Sites with Long-Lived Radionuclides and Greater Than 10 Pore Volumes**

Site	Facility Type	Mobile Constituents	Immobile or Long-Lived Constituents	Number of Pore Volumes	Natural Recharge (mm/yr)	Baseline Information
<b>Uranium-Rich Process Condensate/Process Waste Group</b>						
216-A-5	Crib	U Tc NO3	Pu Cs	557.3	0.5 - 5	1977, 1978
216-A-36A/B	Cribs	U Tc Cr	Pu Am Cs	19.5	0.5 - 5	1977, 1978, 1993
216-A-10	Crib	U Tc I	Pu Am Cs	114.4	0.5 - 5	1977, 1978, 1993
216-C-1	Crib	U Tc	Pu Cs	29.8	50 - 100	
216-S-1&2	Cribs	U Tc NO3	Pu Cs	26.6	50 - 100	1977, 1978
216-B-12	Crib	U Tc	Pu Cs	28.4	50 - 100	1977, 1978, 1993
216-U-8	Crib	U Tc	Pu Cs	34.1	50 - 100	1977, 1978
216-S-7	Crib	U Tc NO3	Pu Cs	46.6	50 - 100	1977, 1978, 1993
216-U-12	Crib	U Tc	Pu Am Cs	107.1	50 - 100	1977, 1978, 1993
216-U-1&2	Cribs	U Tc NO3	Pu Cs	115.5	50 - 100	1977, 1978, 1993
<b>Plutonium-Rich Process Condensate/Process Waste Group</b>						
216-Z-5	Crib	U Tc NO3	Pu Cs	64.6	50 - 100	1977, 1978
216-Z-10	Reverse well	NO3	Pu Am	1000.0	50 - 100	
<b>Plutonium/Organic-Rich Process Condensate/Process Waste Group</b>						
216-Z-3	Crib	U Tc NO3	Pu Cs	409.2	50 - 100	1977, 1978
216-T-19	Tile field/crib	Tc CCl4 NO3	Pu Am Cs	36.4	50 - 100	1977, 1978, 1993
216-Z-12	Crib	U Tc CCl4 NO3	Pu Cs	187.3	50 - 100	1977, 1978, 1993
<b>Organic-Rich Process Condensate/Process Waste Group</b>						
216-A-8	Crib	U Tc	Pu Cs	32.6	50 - 100	1977, 1978
216-A-24	Crib	U Tc	Pu Cs	15.2	50 - 100	1977, 1978, 1993
<b>Fission Product-Rich Process Condensate/Process Waste Group</b>						
216-S-3	Crib	U Tc NO3 Cr	Pu Cs	12.6	50 - 100	
216-B-62	Crib	U Tc	Pu Am Cs	24.4	50 - 100	1977, 1978, 1993
216-B-57	Crib	U Tc	Pu Cs	14.6	10 - 20	1977, 1978, 1993
216-B-11A&B	Reverse wells	U Tc	Pu Cs	174.9	10 - 20	1977, 1978, 1993
<b>General Process Condensate and Process Waste Group</b>						
216-A-37-1	Crib	U Tc NO3	Pu Am Cs	23.7	50 - 100	
<b>Tank Waste Group</b>						
216-T-32	Crib	U Tc NO3	Pu Cs	11.0	50 - 100	1977, 1978
216-T-7	Crib	U Tc NO3	Pu Cs	12.4	50 - 100	1977, 1978
216-T-6	Crib	U Tc NO3	Pu Cs	34.5	50 - 100	1977, 1978, 1993
216-B-7A&B	Cribs	U Tc NO3	Pu Cs	78.1	10 - 20	1977, 1978, 1993
<b>Scavenged Waste Group</b>						
216-T-26	Crib	U Tc CN NO3	Pu Cs	17.6		1977, 1978, 1993
<b>Steam Condensate Group</b>						
216-A-37-2	Crib	U Tc	Am Cs	35.7	50 - 100	
216-S-25	Crib	U Tc NO3	Pu Cs	30.0	10 - 20	1977, 1978
216-B-55	Crib	U Tc	Pu Am Cs	67.5	50 - 100	1977, 1978
216-A-6	Crib	U Tc NO3	Pu Cs	147.7	50 - 100	1977, 1978
216-S-5	Crib	U Tc NO3	Pu Cs	55.6	50 - 100	1977, 1978, 1993
216-S-6	Crib	U Tc NO3	Pu Cs	127.3	50 - 100	1977, 1978, 1993
216-A-30	Crib	U Tc NO3	Pu Am Cs	223.9	50 - 100	1977, 1978, 1993

Table B.3. (contd)

Site	Facility Type	Mobile Constituents	Immobile or Long-Lived Constituents	Number of Pore Volumes	Natural Recharge (mm/yr)	Baseline Information
<b>Chemical Sewer Group</b>						
216-S-11	Pond	U	Pu Cs	20.4	50 - 100	
216-S-10D	Ditch	U	Pu Am Cs	192.2	50 - 100	
216-B-63	Trench	U	Pu Am Cs	658.1	50 - 100	
<b>U Pond/Z Ditches Cooling Water Group</b>						
216-U-10	Pond	U	Pu Am Cs	91.7	50 - 100	
216-Z-20	Crib	Tc NO3	Pu Am Cs	172.7	50 - 100	
<b>Gable Mountain/B Pond and Ditch Cooling Water Group</b>						
216-A-25	Pond	U	Pu Am Cs	445.2		
216-A-9	Crib	U Tc NO3	Pu Cs	48.9	50 - 100	1977, 1978
216-B-3	Pond and ditches	U	Pu Am Cs	105.1	50 - 100	
216-B-2-1	Ditch		Pu Am Cs	1338.0	50 - 100	
<b>200 North Pond Cooling Water Group</b>						
216-N-2	Crib	Tc	Cs	10.3	0.5 - 5	
<b>T Ponds/Ditches Cooling Water Group</b>						
216-T-12	Trench	U Tc	Pu Cs	23.4	0.5 - 5	
<b>200 Areas Chemical Laboratory Waste Group</b>						
216-S-26	Crib	NO3	Am Cs	23.4	50 - 100	
216-U-4A	French drain	U Tc NO3	Pu Cs	27.3	50 - 100	
216-Z-17	Trench	U Tc	Pu	11.1	50 - 100	
216-B-10A	Crib	U Tc NO3 Cr	Pu Cs	21.5	50 - 100	1977, 1978
216-Z-16	Crib	Tc	Pu	44.4	50 - 100	1977, 1978
216-S-20	Crib	U Tc NO3	Pu Cs	22.4	50 - 100	1977, 1978, 1993
216-B-6	Reverse well	Cr		4285.7	50 - 100	
<b>300 Areas Chemical Laboratory Waste Group</b>						
216-T-27	Crib	U Tc NO3	Pu Cs	10.6	50 - 100	1977, 1978, 1993
216-T-28	Crib	U Tc NO3	Pu Cs	62.2	50 - 100	1977, 1978, 1993
<b>Miscellaneous Waste Group</b>						
216-U-3	French drain	U Tc	Pu Cs	20.3	50 - 100	
216-A-21	Crib	U Tc NO3 Cr	Pu Cs	32.8	0.5 - 5	1977, 1978
<b>Sources of Baseline Information</b>						
Fecht et al. (1977).						
Additon et al. (1978a, 1978b).						
Brodeur et al. (1993).						

Brodeur, J. R., R. K. Price, R. D. Wilson, and C. J. Koizumi. 1993. *Results of Spectral Gamma-Ray Logging of Select Boreholes for the 200 Aggregate Area Management Study*. WHC-SC-EN-TI-021, Westinghouse Hanford Company, Richland, Washington.

DOE. 1996. *200 Areas Soil Remediation Strategy - Environmental Restoration Program*. DOE/RL-96-67, U.S. Department of Energy, Richland Operations Office, Richland Washington.

DOE. 1997. *Waste Site Grouping for 200 Areas Soil Investigations*. DOE/RL-96-81, U.S. Department of Energy, Richland Operations Office, Richland, Washington.

DOE Order 5400.1, *General Environmental Protection Program*. U.S. Department of Energy, Washington, D.C.

Downs, J. L., W. H. Rickard, C. A. Brandt, L. L. Cadwell, C. E. Cushing, D. R. Geist, R. M. Mazaika, D. A. Neitzel, L. E. Rogers, M. R. Sackschewsky, and J. J. Nugent. 1993. *Habitat Types on the Hanford Site: Wildlife and Plant Species of Concern*. PNL-8942, Pacific Northwest Laboratory, Richland Washington.

Fayer, M. J., G. W. Gee, M. L. Rockhold, M. D. Freshley, and T. B. Walters. 1996. "Estimating Recharge Rates for a Groundwater Model Using a GIS." *Journal of Environmental Quality* 25:510-518.

Fecht, K. R., G. V. Last, and K. R. Price. 1977. *Evaluation of Scintillation Probe Profiles from 200 Area Crib Monitoring Wells*. ARH-ST-156, Atlantic Richfield Hanford Company, Richland, Washington.

Johnson, V. G., C. J. Chou, and J. W. Lindberg. 1995. *Groundwater Monitoring and Assessment Plan for the 100-K Area Fuel Storage Basins*. WHC-SD-EN-AP-174, Westinghouse Hanford Company, Richland, Washington.

WAC 173-303-645, Washington Administrative Code. *Dangerous Waste Regulations, Releases from Regulated Unit*. Olympia, Washington.

Waite, J. L. 1991. *Tank Wastes Discharged Directly to the Soil at the Hanford Site*. WHC-MR-0227, Westinghouse Hanford Company, Richland, Washington.

**THIS PAGE INTENTIONALLY  
LEFT BLANK**



## **Appendix C**

### **Proposed Fiscal Year 1999 Vadose Zone Monitoring Activities**

**THIS PAGE INTENTIONALLY  
LEFT BLANK**

## **Appendix C**

### **Proposed Fiscal Year 1999 Vadose Zone Monitoring Activities**

Current proposed activities for vadose monitoring in fiscal year 1999 include the following tasks.

- Prepare the detailed, site-specific information, including maps, inventories, constituents of concern, results of previous monitoring, existing subsurface access, existing contamination, applicable regulatory limits, site-specific data quality objectives, and monitoring frequencies.
- Monitor vadose zone contamination beneath about 20 specific retention facilities, using geophysical spectral gamma-ray techniques at specific retention trenches. Report results of the logging effort.
- Complete a feasibility/cost analysis of preferred alternatives for vadose zone monitoring to supplement existing groundwater monitoring at the Liquid Effluent Retention Facility.

**THIS PAGE INTENTIONALLY  
LEFT BLANK**

## Distribution

### No. of Copies

#### OFFSITE

J. Berwick<sup>1</sup>  
U.S. Department of Energy  
Grand Junction Office  
2597 B 3/4 Road  
Grand Junction, Colorado 81503

R. Buck, Jr.<sup>1</sup>  
Wanapum Indian Band  
P.O. Box 878  
Ephrata, WA 98823

S. Harris<sup>1</sup>  
Confederated Tribes of the Umatilla Indian  
Reservation  
P.O. Box 638  
Pendleton, OR 97801

- 2 Nez Perce Tribe<sup>1</sup>  
Nez Perce Tribal Department of  
Environmental Restoration and  
Waste Management  
P.O. Box 365  
Lapwai, ID 83540-0365  
ATTN: D. Powauke  
S. Sobczyk

W. Riggsbee<sup>1</sup>  
Yakama Indian Nation  
Environmental Restoration/Waste  
Management Program  
P.O. Box 151  
Toppenish, WA 98948

### No. of Copies

- 6 U.S. Department of Energy<sup>1</sup>  
Forrestal Building  
1000 Independence Avenue S.W.  
Washington, DC 20585  
ATTN: J. S. Bachmaier (3)  
M. K. Harmon (3) EM-44

#### ONSITE

#### 11 DOE Richland Operations Office

E. M. Bowers <sup>1</sup>	S7-55
B. L. Foley <sup>1</sup>	H0-12
M. J. Furman <sup>1</sup>	H0-12
R. D. Hildebrand <sup>1</sup>	H0-12
R. A. Holton <sup>1</sup>	H0-12
P. E. LaMont <sup>1</sup>	A0-21
R. W. Lober <sup>1</sup>	A2-22
D. E. Olson <sup>1</sup>	H0-12
J. A. Poppiti <sup>1</sup>	S7-54
G. L. Sinton <sup>1</sup>	S7-55
K. M. Thompson <sup>1</sup>	H0-12

#### 5 Bechtel Hanford, Inc.

K. R. Fecht	H0-02
B. H. Ford	H0-21
M. J. Graham	H0-21
A. J. Knepp	H0-21
G. B. Mitchem	H0-17

#### 2 CH2M Hill Hanford, Inc.

V. J. Rohay	H9-02
C. D. Witreich	H9-03

No. of Copies	No. of Copies		
<b>Fluor Daniel Hanford, Inc.</b>		<b>U.S. Environmental Protection Agency</b>	
J. D. Williams	H0-21	T. C. Post	B5-01
<b>Fluor Daniel Northwest, Inc.</b>		<b>Waste Management Federal Services, Inc., Northwest Operations</b>	
F. M. Mann	R1-04	J. E. Meisner H1-13	
M. I. Wood	H6-06		
<b>IT Corporation</b>		<b>34 Pacific Northwest National Laboratory</b>	
D. A. Myers	R1-04	R.W. Bryce	K6-75
<b>Lockheed Martin Hanford Corporation</b>		J. G. Bush	K6-96
E. A. Fredenburg		M. J. Fayer	K9-33
		G. W. Gee	K9-33
E. A. Fredenburg		G. R. Holdren	K6-81
		D. G. Horton (10) <sup>1</sup>	K6-81
<b>MACTEC-ERS</b>		V. G. Johnson	K6-96
J. F. Bertsch		G. V. Last <sup>1</sup>	K6-81
		P. E. Long	K6-91
<b>3 State of Washington Department of Ecology</b>		C. J. Murray	K6-81
		T. L. Page	K9-18
L. J. Cusack		S. P. Reidel <sup>1</sup>	K6-81
		R. J. Serne	K6-81
L. J. Cusack	B5-18	R. M. Smith	K6-96
S. L. Dahl-Crumpler	B5-18	M. D. Sweeney	K6-81
D. N. Goswami	B5-18	A. L. Ward	K9-33
		G. Whelan	K9-36
		B. A. Williams	K6-81
		Information Release Office (7)	K1-06

<sup>1</sup> Hard-copy distribution has been made to these individuals. Distribution to all other individuals was made electronically through <http://www.pnl.gov/vadose/index.html>.